

UNCLASSIFIED
EXCLUDED FROM AUTOMATIC
DOWNGRADING AND
DECLASSIFICATION
PROCESSING



PROGRAM MANAGER RMA CONTAMINATION CLEANUP

U.S. ARMY
MATERIEL COMMAND

— COMMITTED TO PROTECTION OF THE ENVIRONMENT —

Composite Well Program
Task 1, Task 11, Task 19, Task 21,
Task 22, Task 25, Task 26, Task 36,
Task 38, Task 39, Task 42, Task 44

Draft Final Report
(Version 2.3)
July 1988
Contract Number DAAK11-84-D-0016
(as part of Task 44)

FILE COPY

Environmental Science And Engineering, Inc.


Rocky Mountain Arsenal
Information Center
Commerce City, Colorado

REQUESTS FOR COPIES OF THIS DOCUMENT
SHOULD BE REFERRED TO THE PROGRAM MANAGER
FOR THE ROCKY MOUNTAIN ARSENAL CONTAMINATION CLEANUP,
AMXRM ABERDEEN PROVING GROUND, MARYLAND

DTIC QUALITY INSPECTED 5

LITIGATION TECHNICAL SUPPORT AND SERVICES

Rocky Mountain Arsenal



Composite Well Program
Task 1, Task 11, Task 19, Task 21,
Task 22, Task 25, Task 26, Task 36,
Task 38, Task 39, Task 42, Task 44


Draft Final Report
(Version 2.3)
July 1988
Contract Number DAAK11-84-D-0016
(as part of Task 44)

PREPARED BY

ENVIRONMENTAL SCIENCE & ENGINEERING, INC.

PREPARED FOR:

U.S. PROGRAM MANAGER'S OFFICE FOR
ROCKY MOUNTAIN ARSENAL



THE VIEWS, OPINIONS, AND/OR FINDINGS CONTAINED IN THIS REPORT ARE THOSE OF THE AUTHOR(S) AND SHOULD NOT BE CONSTRUED AS AN OFFICIAL DEPARTMENT OF THE ARMY POSITION, POLICY, OR DECISION, UNLESS SO DESIGNATED BY OTHER DOCUMENTATION.


THE USE OF TRADE NAMES IN THIS REPORT DOES NOT CONSTITUTE AN OFFICIAL ENDORSEMENT OR APPROVAL OF THE USE OF SUCH COMMERCIAL PRODUCTS. THIS REPORT MAY NOT BE CITED FOR PURPOSES OF ADVERTISEMENT.

1995 11 15 107

REPORT DOCUMENTATION PAGE			Form Approved OMB No. 0704-0188	
Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the data needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.				
1. AGENCY USE ONLY (Leave blank)		2. REPORT DATE 07/00/88		3. REPORT TYPE AND DATES COVERED
4. TITLE AND SUBTITLE COMPOSITE WELL PROGRAM, TASK 1, TASK 11, TASK 19, TASK 21, TASK 22, TASK 25, TASK 26, TASK 36, TASK 38, TASK 39, TASK 42, TASK 44, DRAFT FINAL REPORT, VERSION 2.3			5. FUNDING NUMBERS	
6. AUTHOR(S) <i>no report for this one!</i>			7. PERFORMING ORGANIZATION REPORT NUMBER DAAK11 84 D 0016	
7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES) ENVIRONMENTAL SCIENCE AND ENGINEERING DENVER, CO			8. PERFORMING ORGANIZATION REPORT NUMBER 88244R02	
9. SPONSORING/MONITORING AGENCY NAME(S) AND ADDRESS(ES) ROCKY MOUNTAIN ARSENAL (CO.). PMRMA COMMERCE CITY, CO			10. SPONSORING/MONITORING AGENCY REPORT NUMBER	
11. SUPPLEMENTARY NOTES				
12a. DISTRIBUTION/AVAILABILITY STATEMENT APPROVED FOR PUBLIC RELEASE; DISTRIBUTION IS UNLIMITED			12b. DISTRIBUTION CODE	
13. ABSTRACT (Maximum 200 words) 200 ALLUVIAL AND DENVER AQUIFER WELLS AT 120 SITES HAVE BEEN PROPOSED UNDER 12 TASKS. THE COMPOSITE WELL PROGRAM (CWP) WAS ESTABLISHED UNDER TASK 44 TO PREVENT DUPLICATION OF WELL ACTIVITIES AND TO MAXIMIZE RESOURCES. THE CWP EVALUATED THE TASK SPECIFIC NEEDS WITH RESPECT TO THE OVERALL RMA HYDROLOGIC ASSESSMENT TO ENSURE ALL REQUIREMENTS FOR THE RESPECTIVE TASKS WERE FULFILLED, AS WELL AS MAKING SURE DATA GAPS IN THE REGIONAL SCHEME WERE SATISFIED. THIS REPORT PRESENTS TASK OBJECTIVES FOR TASKS 1, 11, 19, 21, 22, 25, 26, 36, 38, 39, 42, AND 44. FOR EACH WELL PROPOSED IN THESE TASKS, THE PROPOSED LOCATION AND RATIONALE FOR DRILLING ARE GIVEN. APPENDICES INCLUDE: 1. ON-POST WELL PRIORITY RATIONALE 2. OFF-POST WELL PRIORITY RATIONALE 3. WELL STATUS 4. DEEP WELL METHODOLOGY.				
14. SUBJECT TERMS GROUNDWATER MONITORING, RMA ELEVATION CONTOUR MAP			15. NUMBER OF PAGES	
			16. PRICE CODE	
17. SECURITY CLASSIFICATION OF REPORT UNCLASSIFIED		18. SECURITY CLASSIFICATION OF THIS PAGE		19. SECURITY CLASSIFICATION OF ABSTRACT
20. LIMITATION OF ABSTRACT				

19951115 107

DISCLAIMER NOTICE



**THIS DOCUMENT IS BEST
QUALITY AVAILABLE. THE
COPY FURNISHED TO DTIC
CONTAINED A SIGNIFICANT
NUMBER OF PAGES WHICH DO
NOT REPRODUCE LEGIBLY.**

TABLE OF CONTENTS

Section	Page
1.0 INTRODUCTION	1-1
1.1 PROGRAM SUMMARY	1-1
1.2 COMPOSITE WELL PROGRAM (CWP)	1-10
1.2.1 CRITERIA	1-11
1.2.2 INSTALLATION PRIORITY	1-12
2.0 TASK 1	2-1
2.1 OBJECTIVES	2-1
2.2 PROPOSED LOCATIONS	2-2
3.0 TASK 11	3-1
3.1 OBJECTIVES	3-1
3.2 PROPOSED LOCATIONS	3-2
4.0 TASK 19	4-1
4.1 OBJECTIVES	4-1
4.2 PROPOSED LOCATIONS	4-1
5.0 TASK 21	5-1
5.1 OBJECTIVES	5-1
5.2 PROPOSED LOCATIONS	5-2
6.0 TASK 22	6-1
6.1 OBJECTIVES	6-1
6.2 PROPOSED LOCATION	6-1
7.0 TASK 25	7-1
7.1 OBJECTIVES	7-1
7.2 PROPOSED LOCATIONS	7-1
8.0 TASK 26	8-1
8.1 OBJECTIVES	8-1
8.2 PROPOSED LOCATIONS	8-1
9.0 TASK 36	9-1
9.1 OBJECTIVES	9-1
9.2 PROPOSED LOCATIONS	9-1

Accession For	
NTIS CRA&I	<input checked="" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A-1	

10.0 TASK 38	10-1
10.1 OBJECTIVES	10-1
10.2 PROPOSED LOCATIONS	10-2
11.0 TASK 39	11-1
11.1 OBJECTIVES	11-1
11.2 PROPOSED LOCATIONS	11-2
12.0 TASK 42	12-1
12.1 OBJECTIVES	12-1
12.2 PROPOSED LOCATIONS	12-2
13.0 TASK 44	13-1
13.1 OBJECTIVES	13-1
13.2 PROPOSED LOCATIONS	13-2

APPENDICES

APPENDIX A--ONPOST WELL PRIORITY RATIONALE
APPENDIX B--OFFPOST WELL PRIORITY RATIONALE
APPENDIX C--STATUS
APPENDIX D--DEEP WELL METHODOLOGY

LIST OF PLATES

- Plate 1 Composite Well Program Proposed Location
- Plate 2 On and Offpost Ground Water Monitoring
Well Location Map, February 1987
- Plate 3 Rocky Mountain Arsenal Bedrock Elevation Contour Map
- Plate 4 Ground-Water Monitoring Network, Spring 1987

1.0 INTRODUCTION

1.1 PROGRAM SUMMARY

The Comprehensive Hydrologic Monitoring Program at Rocky Mountain Arsenal (RMA) is two-dimensional in function. As such, it is designed to accomplish the basic objectives of:

- o Regional monitoring; and
- o Site/source specific monitoring.

The regional component is directed to long-term hydrologic monitoring onpost at and offpost of RMA. As designed, it will provide the data necessary to monitor the water quality and hydraulic regime of the area. Conversely, site/source specific monitoring addresses the need for collection of detailed hydrologic data required to complete a site specific assessment. The efforts supplement the regional aspect of the program by providing additional hydrologic information at selected areas of RMA.

Under the ongoing cleanup effort at RMA, several hydrologic and/or hydrologic-related tasks have been or are currently being performed.

Task 4 - RMA Water Quantity/Quality Survey

Objectives

Under this task, a one-year ground-water and surface water surveillance program was performed at RMA to achieve the following objectives:

- o Satisfy the requirements of the Comprehensive Environmental Response, Compensation, and Liability Act of 1980 (CERCLA) and the substantive requirements of all applicable or relevant and appropriate Federal and State requirements that have application through CERCLA;
- o Confirm the existence and chemical nature of known contamination and monitor any changes in the lateral and vertical extent of contaminant migration; and
- o Develop a core data base for use in upcoming litigation and Remedial Investigation/Feasibility Study (RI/FS) analyses for RMA.

Scope-of-Work

The purpose of the Task 4 Water Quantity/Quality Survey was to execute a one-year ground-water and surface water surveillance program capable of satisfying the various regulatory requirements, developing a litigation quality data base, and verifying the extent and nature of known contamination. In order to achieve these objectives, five distinct technical elements were conducted. These were as follows:

- o Review historical data;
- o Develop a monitoring program to achieve the above objectives;
- o Execute the monitoring program utilizing litigation quality sampling and analytical procedures;
- o Assess data quarterly for possible adjustments in the monitoring program; and
- o Compile the accumulated data at the end of the one-year program.

Data were collected during the period of October 1985 to September 1986. Efforts included an initial sampling of 320 onpost wells between October 1985 and March 1986, and two additional quarters of sampling (April to June 1986 and July to September 1986) from 188 wells. Water levels were obtained quarterly from 800 wells. No monitoring wells were installed under this task.

Task 25 - RMA Boundary Systems Monitoring**Objectives**

The objectives of Task 25 were to monitor ground-water flow and contaminant transport in and around the North and Northwest Boundary Containment Systems (NBCS and NWBCS), to define contaminant pathways in these areas, and provide chemical and hydrologic data for the operation of the NBCS and NWBCS.

Scope-of-Work

The scope-of-work for Task 25 included:

- o A detailed geologic study of the Denver Formation (Fm) and the alluvial aquifer. This study entailed the construction of isopach maps, cross sections, structure contour maps, and other types of diagrams. It defined the configuration and extent of various rock and soil units that are important to the hydrogeologic framework of the boundary area and the migration of contaminants;

07/12/88

- o Monitoring of wells to determine the distribution and concentration of contaminants and the configuration of piezometric surfaces associated with specific aquifers; and
- o Maps showing contaminants distribution and the configurations of piezometric heads along with pertinent geologic and hydrologic data to support the operations of the NBCS and NWBCS enabling them to increase operating efficiencies.

Data were collected for the period of September 1986 through December 1987. Water quality sampling was performed at some 145 wells and water levels monitored at over 350 wells on a quarterly basis. Monitoring wells were proposed at 21 sites. Wells were installed at nine of the proposed locations. All wells were alluvial completions.

Task 26 - Ground-Water Treatment Study/Interim Action Assessment
Objectives

The objectives of Task 26 were to evaluate the ground-water flow systems in the South Plants, Basin A, and Basin A Neck region; to identify areas in this region for implementing Interim Response Actions (IRAs); and, to prepare an assessment of alternatives for the design and construction of an alluvial ground-water intercept and treatment system in the Basin A Neck area.

Scope-of-Work

The focus of the task has been revised twice. Originally a feasibility study evaluating the ground-water flow systems and developing conceptual ground-water collection and treatment systems for the South Plants and Basin A areas, the task was changed to an Alternatives Assessment for an IRA in the Basin A Neck area. The focus of the task was to evaluate appropriate alternatives for a ground-water intercept and treatment system, to select the most cost effective alternative for attaining the objective of the IRA, and to identify additional data required to design and implement the IRA.

Task 36 - North Boundary System Component Response Assessment
Objectives

The objectives of Task 36 were to evaluate the adequacy of the dewatering and recharge components of the North Boundary System through a review of the

07/13/88

operational data and evaluation of additional geotechnical data; assess the configuration of the Denver Fm sandstones and evaluate their hydrologic characteristics, especially in the area of the Pilot System, through the acquisition and evaluation of additional geologic and hydrologic data; assess the physical condition of the soil-bentonite barrier through in-situ and laboratory testing, especially in areas suspected of having problems, which consider physical and chemical degradation of the wall; and assess the adequacy of the carbon-adsorption type treatment system to effectively remove contaminants to appropriate cleanup goals through the analysis of effluent water samples.

Scope-of-Work

Task 36 characterized the geologic regime in the vicinity of the NBCS using data from previous investigations and additional data collected as part of this task. Where historical data was lacking, soil borings were drilled and soil and rock samples collected. Particular attention directed to the areal extent and position of Denver sand units.

In addition to the geologic characterization, a hydrologic evaluation was performed using primarily water level and quality data. Much of these data were collected as part of the regional Water Quantity/Quality Survey (Tasks 4 and 44) and the Boundary Systems Monitoring (Task 25) tasks. To complement the information available from these tasks and fill data deficiencies, the scope-of-work included installation, development, and sampling of new ground-water monitoring wells in selected locations. These efforts resulted in the completion of 19 wells at 11 sites. Of the new wells, 3 were alluvial, 10 first Denver, and 6 second Denver wells. Completions at 7 of the 11 sites were clusters. Additionally, 10 piezometers were installed under the task. As these new wells were completed and developed, they were sampled for water quality parameters to aid in the identification of other locations for which monitoring wells provided valuable information, and they were sampled in coordination with Tasks 25 and 44 sampling events to provide integrated data sets. Some 70 samples were collected.

Using the data described above, an assessment of the hydrologic conditions in the vicinity of the NBCS was performed. This included an assessment of

07/12/88

both dewatering and recharge components of the NBCS and the hydrologic relationship between saturated portions of the alluvium and the Denver Fm, using such tools as the ground-water management flow model developed by Jim Warner of Colorado State University.

The carbon-adsorption type water treatment plant was evaluated to ensure that contaminants intercepted can be treated to appropriate cleanup goals. This evaluation included the analysis of effluent water samples for water quality. In addition, turbidity tests on the effluent water were conducted to evaluate what effect carbon fines may have on plugging of the recharge wells.

To complete the assessment of the NBCS, the Task 36 scope-of-work included an evaluation of the physical condition, integrity, and hydrologic properties of the soil-bentonite barrier. Samples of the barrier were collected and subjected to both physical and hydrologic testing. This data, in conjunction with results of the geologic and hydrologic assessment, allowed evaluations of the effectiveness of the barrier.

Upon completion of data assessment, conceptual response actions which may enhance system performance were developed and evaluated.

Task 38 -- Western Tier TCE Study

Objectives

The objectives of Task 38 were to perform field and literature investigations of the Western Tier of RMA in order to support current litigation between the United States and the State of Colorado; determine the source(s), if any, of trichloroethene (TCE) in the Western Tier of RMA; if a source exists, define the contaminant plume between the source and the RMA boundary; and estimate the present contribution of TCE concentration from RMA to the offpost South Adams County TCE contamination.

Scope-of-Work

Task 38 included the compilation of all historical information regarding TCE storage and usage in the western third of RMA, sampling of 36 soil borings, installation of 32 ground-water monitoring wells, 2 separate soil gas surveys, a geophysical program, periodic water level measurements from 102

07/12/88

to 150 wells, and several rounds of ground-water sampling. Site 4-6 was also investigated under Task 38 at which 36 soil borings were drilled and 169 samples collected, including 1 soil grab sample and 3 surface water samples.

Petrex static tube soil gas samplers were placed at about 1,000 locations throughout the Western Tier for a soil gas study. For a separate soil gas study, 256 Tracer Research soil gas samples were collected and analyzed for 1,1,1-trichloroethane (TCA), TCE, and tetrachloroethane (PCE). Twenty-seven of these were analyzed for benzene, toluene, ethyl benzene, and xylenes.

Soil samples were analyzed for standard Phase I compounds including volatile and semivolatile organics (GC/MS), ICP metals, and mercury and arsenic (AA). Water samples were analyzed for volatile halogenated organics (GC/CON), volatile aromatic organics (GC/PID), DBCP (GC/ECD), and nitrates (technicon).

Task 39 - Offpost RI/FS

Objectives

The objectives of Task 39 were to conduct a RI/FS and Endangerment Assessment (EA) in the offpost study area and determine contaminant distribution for input to an EA as support for the FS. This task is primarily concerned with ground-water contamination although air, soil/sediment, biota, and surface water will be considered. Product of task will be support for a Record of Decision.

Scope-of-Work

Thirteen of 29 proposed sites were drilled for the installation of monitoring wells in the offpost area. Geotechnical efforts resulted in the installation of 19 wells. Seventeen were alluvial, 1 first Denver, and 1 second Denver completions. One cluster site was utilized. Two sampling events were conducted and the samples analyzed. Surface water, soils, and sediments were sampled during the investigation.

Based upon the results of the sample analyses during the RI, an EA and FS were conducted. The FS was oriented toward protection of human health and the environment by remediation of contaminated ground water.

07/12/88

Task 42 - North Plants Survey**Objectives**

The objectives of Task 42 were to:

- o Assess whether soil or ground water had been contaminated by North Plants operations;
- o Identify the constituents present; and
- o Conduct a preliminary evaluation of the vertical and horizontal extent of contamination, if present.

Scope-of-Work

The emphasis of the task was on soils, however six alluvial ground-water monitoring wells were also installed. Ground-water samples were collected and analyzed for volatile aromatics, volatile halogens, semivolatiles, phosphonates, organosulfur compounds, thiodiglycol, cadmium, chromium, copper, lead, zinc, arsenic, mercury, magnesium, calcium, sodium, potassium, sulfate, nitrate, chloride, fluoride, and phosphate.

Task 44 - RMA Onpost/Offpost Ground Water/Surface Water Monitoring Program**Objectives**

As part of the environmental investigation at RMA, the necessity of establishing a litigation-quality data base for surface and ground water has been recognized. Task 4 addressed part of this need by providing baseline data to assess contaminant distributions at RMA.

Under Task 4, three rounds of water samples were collected over a 1-year period within RMA to achieve the following objectives:

- o Satisfy the requirements under CERCLA and the substantive requirements of all applicable or relevant and appropriate Federal and State requirements that have application through CERCLA;
- o Confirm the existence and chemical nature of contamination and monitor any changes in the lateral and vertical extent of contamination; and
- o Develop a core data base for use in upcoming litigation and RI/FS analyses for RMA.

07/12/88

Task 44 was developed using the core Task 4 objectives; however, the scope of the task has been broadened to address other salient items that were beyond the scope of Task 4.

The objectives of Task 44 as detailed in the Delivery Order were to:

- o Assess the distribution and concentration levels of ground-water contaminants and monitor changes in water quality with respect to these contaminants for both the onpost and offpost areas using established contaminant guidance levels;
- o Monitor and evaluate changes in water levels;
- o Evaluate data and recommend program modifications to this or other water monitoring tasks; and
- o Identify areas of significant public exposure by comparison of offpost water quality results with current guidance levels.

In order to satisfy the primary goals of the task, certain ancillary objectives were accomplished. Additionally, these efforts further defined the Task 44 scope-of-work:

- o Utilize available geologic data to further define the current understanding of the geologic conditions present at RMA;
- o Summarize the hydrogeologic conditions in the onpost and offpost areas by integrating existing hydrologic, geologic, and water quality data;
- o Assess the distribution of contaminants in aqueous media and identify the primary hydrogeologic pathways by which contaminants are being transported to the RMA boundary or the offpost area;
- o Evaluate the existing monitoring program for data deficiencies and assess the need for additional wells; and
- o Integrate all data from water related tasks and supply appropriate information to Task 23 efforts including data bases, contaminant plume maps, and hydrogeologic assessments.

Task 44 established the hydrologic core data base for and provided to the EA and FS groups adequate interpretation and characterization of hydrologic, geologic, and geochemical data so that their specified goals were achieved.

07/12/88

The overall Task 44 program was designed to be dynamic in nature and was modified, as required, in response to ongoing data evaluation and/or changes in the scope-of-work or task objectives. Task 44 formed the base or trunk hydrologic program, while other efforts (Tasks 25, 36, 38, 39, etc.) were tributary or branch efforts which satisfied specific individual task needs, as well as augmented the Task 44 program.

In addition to 27 square miles (sq mi) of onpost area covered by Task 44, 14 sq mi of the offpost area were monitored. The offpost area extends northwestward from RMA to the South Platte River. Several other detailed ground-water tasks address localized areas within the Task 44 study area.

Scope-of-Work

The purpose of this task was to perform a hydrologic assessment of the RMA onpost and offpost areas. This assessment included development of a baseline program for hydrologic and contamination surveillance. Network design was followed by collection of surface water and ground-water samples, measurement of hydrologic parameters, and chemical analysis of water samples. These data were evaluated to document the extent of contamination, the hydrologic and geologic conditions of the site, areas of public health exposure, potential contaminant migration pathways, and areas where additional data are required.

The scope of the Task 44 water quantity/quality survey included completing a semiannual and/or quarterly ground-water and surface water monitoring program capable of satisfying the various regulatory requirements, developing litigation-quality data to be added to the current data base, and assessing the extent and nature of contamination. In order to achieve these objectives, work in six distinct technical areas was anticipated. These areas are as follows:

- o Review the historical data;
- o Develop a monitoring program to achieve the objectives in Section 1.2 of the Task 44 Technical Plan;
- o Execute the monitoring program utilizing litigation-quality sampling and analytical procedures;
- o Assess data after the first sampling event for possible adjustments in the sampling and/or analytical scheme;

07/13/88

- o Compile and interpret the accumulated data at the end of the sampling program;
- o Coordinate with and integrate data from other current ground-water tasks such as Tasks 25, 26, 36, 38, and 39; and
- o Identify data gaps and, when possible, rectify.

In the performance of the task, 21 wells were installed at 10 of the 20 proposed sites. Resulting from these efforts was the completion of 4 alluvial, 9 first Denver, and 8 second Denver wells. Seven clusters were completed.

Additional Water Related Programs

Included as part of various soil investigation tasks scope-of-work was the requirement for hydrologic monitoring at selected source areas. Under these efforts, water quality and hydraulic monitoring was performed at existing or newly installed ground-water wells in order to determine potential soil/water interactions. Activities as described were conducted under Tasks 1, 19, and 21.

1.2 COMPOSITE WELL PROGRAM (CWP)

As detailed in the Task 44 Technical Plan (ESE, 1988, RIC#88063R11), one of the ancillary objectives of the task was to coordinate the hydrologic activities performed under various RI/FS efforts. A major component of the task was the installation and/or replacement of monitoring wells. Currently, some 200 alluvial and Denver aquifer wells at 120 sites have been proposed under Tasks 1, 19, 21, 25, 36, 39, and 44. As detailed previously, with the exception of the Task 44, a regional activity, the other programs are localized and as such possess site specific requirements. Under this scheme, the potential for duplication of efforts in some areas, while other areas are overlooked, becomes possible. In order to circumvent these potential problems and to maximize resources while minimizing schedule, the Composite Well Program (CWP) was established under Task 44. As such, the CWP evaluated the task specific needs with respect to the overall RMA hydrologic assessment to ensure all requirements for the respective tasks were fulfilled, as well as making sure data gaps in the regional scheme were satisfied.

As designed, the CWP represents a compilation of all proposed well installation activities for the following tasks:

- o Task 1;
- o Task 11;
- o Task 19;
- o Task 21;
- o Task 22;
- o Task 25;
- o Task 26;
- o Task 36;
- o Task 38;
- o Task 39;
- o Task 42; and
- o Task 44.

1.2.1 CRITERIA

The primary criterion for determining the need for additional wells was based on an evaluation of task objectives and the data required to achieve these. Following development of the respective Technical Plans, an evaluation of the available data versus required data to satisfy task objectives was performed. Where data gaps existed, wells were proposed to provide the necessary information. These gaps included the need for additional:

- o Geologic;
- o Hydrologic;
- o Contaminant Characterization; or
- o Plume Definition Data.

Once the requirement for additional wells was established the study area of the task was evaluated based on its geology, hydrology, contaminant characterization and distribution, and the condition of the existing wells in the area. These evaluations required compilation and analysis of:

- o Cross sections;
- o Isopach maps;
- o Water table elevations;
- o Ground-water flow directions;
- o Saturated thickness;

- o Bedrock surface;
- o Alluvial thickness;
- o Contaminant distribution; and
- o Well construction data.

Following completion of the above evaluations, well sites were proposed. The proposed well locations are illustrated in Plate 1.

The current status of the CWP is detailed in Appendix C.

1.2.2 INSTALLATION PRIORITY

In order to optimally perform the extensive well installation program compiled under the CWP, a priority system utilizing a phased approach was established. The scheme was designed to categorize each well or corehole based on its contribution to satisfying primary task objectives. Installations deemed essential to the achievement of the task were designated as primary and were completed initially. Wells and coreholes defined as secondary are installations which may be more effectively undertaken following an evaluation of the geologic and hydrologic data obtained through completion of the primary sites. Tertiary installations are those which may be drilled, if deemed necessary, following a review of the data collected through completion of the primary and secondary sites. Appendices A and B present the priority rationale for the proposed sites.

The CWP is designed to be dynamic in nature and will be modified as the ongoing geologic, hydrologic, and contamination assessments warrant. Based on continuing data review, assigned priorities may change and/or installations may be eliminated from the program.

07/12/88

2.0 TASK 1

2.1 OBJECTIVES

Phase I soils data indicate that a relationship may exist between chemical levels in the unsaturated zone and observed levels of these same compounds in downgradient ground water. These relationships may be particularly important and complex where a body of soil containing chemicals exists immediately above and possibly within the saturated zone. Site 36-1 (Basin A) and Sites 36-3, 36-4, and 36-17 are the best examples of this situation. Phase I soil boring data from these sites indicate high levels of arsenic, mercury, pesticides, and munitions. Existing water data also suggest elevated analyte concentrations in downgradient locations.

The proposed plan for installation of monitoring wells in Section 36 has several objectives derived from Task 1 and Task 4. These objectives can be briefly stated as:

- o Providing monitoring points required to investigate the possible contributions to ground-water contamination from Sites 36-1, 36-3, 36-4, and 36-17;
- o Establishing control points for the measurements of ground-water levels and chemical constituents in the eastern third of Section 36; and
- o Defining geology and hydrology in poorly characterized areas which may be significant migration pathways.

All of these objectives support the upcoming effort to combine and correlate soil and ground-water data already obtained. Monitoring wells will be sited based on Phase I data in order to monitor upgradient and downgradient conditions at sites. Wells will be placed to best advantage to investigate ground-water flow patterns and the possible presence of bedrock channels which have been suggested through previous geologic mapping.

2.2 PROPOSED LOCATIONS

Site EP-35

Location: Proposed well site EP-35 is located 100 feet (ft) north of the south line, 680 ft east of the west line in Section 36, T2S R67W.

Rationale: The proposed well will replace existing Well 36001. The approximate location is Basin A (Site 36-1) upgradient alluvial, intermediate, and lower aquifer characterization. Existing Well 36001, of undocumented construction, exhibits high contaminant concentrations potentially related to the South Plants area ground-water contamination, surface runoff, or leakage from the contaminated sewer. These wells will complement additional shallow wells along the section line which have been proposed by Task 26.

Site EP-36

Location: Proposed well site EP-36 is located 200 ft north of the south line, 3,000 ft east of the west line in Section 36, T2S, R67W.

Rationale: Insecticide Pits (Site 36-3) upgradient alluvial aquifer characterization. Site EP-36 is located to supplement Well 36075, which is rated as questionable construction. The well will screen the entire saturated alluvium which is approximately 10-ft thick in this area.

Site EP-37

Location: Proposed well site EP-37 is located 1,750 ft north of the south line, 2,450 ft west of the east line in Section 36, T2S, R67W.

Rationale: Mustard Disposal Area (Site 36-17) downgradient alluvial aquifer characterization. Site EP-37 will determine the presence of mustard degradation products.

Site EP-38

Location: Proposed well site EP-38 is located 2,450 ft south of the north line, 2,350 ft west of the east line in Section 36, T2S, R67W.

07/12/88

Rationale: Reactor Vessel Area (Site 36-17) downgradient alluvial aquifer characterization. Site EP-38 will determine the presence of contaminants due to upgradient reactor vessel disposal. The site is located to supplement Well 36084 which is of questionable construction. The saturated alluvium is approximately 15-ft thick in this area, so the screen length will be 17 ft.

Site EP-39

Location: Proposed well site EP-39 is located 2,605 ft north of the south line, 1,900 ft west of the east line in Section 36, T2S, R67W.

Rationale: Reactor Vessel Area (Site 36-17) upgradient alluvial aquifer characterization. Site EP-39 will determine upgradient water quality in the area of Basin A. The screen length will be 12 ft as the saturated alluvium is approximately 10-ft thick.

Site EP-41

Location: Proposed well site EP-41 is located 1,500 ft south of the north line, 400 ft east of the west line in Section 36, T2S, R67W. Additionally, the well is 100 ft east of Well 36017.

Rationale: Basin A (Site 36-1) downgradient alluvial, intermediate, and lower aquifer characterization. Site EP-41 will be along the Basin A outflow, and will supplement many poorly documented wells in this area.

3.0 TASK 11

3.1 OBJECTIVES

The objective Task 11 was to conduct a contamination survey of the soil and ground water in the vicinity of the Hydrazine Blending Storage Facility (HBSF) and provide information necessary to assess the nature and extent of contamination in the HBSF. This information was utilized in the general assessment of contamination at RMA overseen by PMO, and in the more specific context of Task 13, which includes a Resource Conservation and Recovery Act (RCRA) closure plan for the HBSF. The Task 11 Technical Plan was developed to provide pertinent information for (1) the preparation of a RCRA closure plan, which requires continued ground-water monitoring, and (2) the overall assessment of the extent of contamination at RMA.

The initial portion of the Task 11 work program was an extensive literature review to develop a complete history of the activities at the HBSF and of previous studies. Data obtained from this literature review details the physical, chemical and environmental histories of the HBSF. This information was used to support a geotechnical program which evaluated existing ground-water monitoring and soils sampling networks with respect to the requirements of a RCRA closure plan.

Water levels were measured in the existing monitoring wells located within 500 ft of the HBSF. This information was incorporated into the Task 11 study to develop preliminary information on flow patterns in the shallow ground-water system. By incorporating the ten existing wells into the closure plan, the HBSF was surrounded with monitoring wells both upgradient and downgradient of the source. Two additional wells within HBSF were required to monitor the ground water beneath the potential source. Ground-water flow patterns along with the semiquantitative results of the soil boring program were used to determine the locations of the two new wells proposed for installation at the HBSF under Task 11.

3.2 PROPOSED LOCATIONS

Site_HSBF-1

Location: Proposed well site HSBF-1 is located 480 ft south of the north line and 1,450 ft west of the east line of Section 1, T3S, R67W.

Rationale: Required to satisfy regulatory monitoring requirements.

Site_HSBF-2

Location: Proposed well site HSBF-2 is located 400 ft south of the north line and 250 ft west of the east line of Section 1, T3S, R67W.

Rationale: Required to satisfy regulatory monitoring requirements.

4.0 TASK 19

4.1 OBJECTIVES

Phase I soils data indicate that a relationship may exist between chemical levels in the unsaturated zone and observed levels of these same compounds in downgradient ground water. These relationships may be particularly important and complex where a body of soil containing chemicals exists immediately above and possibly within the saturated zone. Basins B through F (Sites 35-3, 26-3, 26-4, 26-5, and 26-6) are examples of this situation.

The proposed plan for installation of monitoring wells in Sections 26 and 35 has several objectives. These objectives can be briefly stated as:

- o Providing monitoring points required to investigate the possible contributions to ground-water contamination from Sites 35-3, 26-3, 26-4, 26-5, and 26-6;
- o Establishing control points for the measurements of ground-water levels and chemical constituents in Section 26 and the northeastern part of Section 35;
- o Defining the paleotopographic surface of the bedrock, the geology, and the hydrology in poorly characterized areas; and
- o Defining the vertical extent of analytes in Section 26 and the northeast quarter of Section 35.

All of these objectives support the upcoming effort to combine and correlate soil and ground-water data already obtained. Monitoring wells have been sited based on Phase I data in order to monitor upgradient and downgradient conditions at sites. Wells have been carefully placed to investigate ground-water flow patterns and the possible presence of bedrock channels which have been suggested through previous geologic mapping. The elevation and paleotopography of the underlying bedrock surface will also be investigated.

4.2 PROPOSED LOCATIONS

Site EP-42

Location: Proposed well site EP-42 is located 375 ft south of the north line, 1,400 ft west of the east line, Section 35, T2S, R67W.

Rationale: Basin B (Site 35-3) downgradient alluvial aquifer characterization. Site EP-42 will be located to establish water quality beneath Basin B. The water table occurs approximately 10 to 15 ft below ground surface. The screen will be placed at the water table in the saturated alluvial material. It is anticipated that this well will correlate with Wells 35044 and 35046 which are completed in the upper Denver Fm.

Site EP-43

Location: Proposed well site EP-43 is located 800 ft north of the south line, 1,300 ft west of the east line, Section 26, T2S, R67W.

Rationale: Basin C (Site 26-3) upgradient water table aquifer characterization. Site EP-43 will be located east of the basin boundary to establish water quality in the area of Basin C. The water table occurs at or slightly above the bedrock surface, or approximately 30 ft below ground surface. The screened interval will be within the saturated, fractured clayshale unit at the top of the Denver Fm. Wells in this area (26057, 26058, 26063, 26064, 26096) are all screened in the upper or lower Denver sands and do not reflect alluvial aquifer characteristics.

Site EP-44

Location: Proposed well site EP-44 is located 200 ft north of the south line, 2,500 ft east of the west line, Section 26, T2S, R67W.

Rationale: Basin D (Site 26-4) upgradient, and Basins B and C (Sites 35-3 and 26-3) downgradient alluvial and Denver aquifer characterization. The alluvial well will be screened below the water table in the fractured clayshale at the alluvium/bedrock contact. Based on well log 26060, the lower Denver sand is anticipated to occur in the 80- to 100-ft interval. A lower zone will also be screened to determine the vertical extent of contamination. No well logs are available which extend below the lower sand of the Denver Fm. Total depth of this well will not exceed 150 ft.

07/12/88

Site EP-45

Location: Proposed well site EP-45 is located 1,200 ft north of the south line, 1,550 ft east of the west line, Section 26, T2S, R67W.

Rationale: Basin D (Site 26-4) downgradient water table aquifer characterization. Site EP-45 will be located in the northwest corner of Basin D to establish water quality downgradient of the basin. The water table occurs at or slightly below the bedrock surface, or approximately 30 ft below ground surface. This well will be screened in the fractured clayshale of the upper Denver Fm. Site EP-45 will correlate with strata penetrated by Wells 26005 and 26068.

Site EP-46

Location: Proposed well site EP-46 is located 950 ft north of the south line, 800 ft east of the west line, Section 26, T2S, R67W.

Rationale: Basin E (Site 26-5) upgradient water table aquifer characterization. Site EP-46 will be located immediately southeast of the basin boundary to establish water quality upgradient of Basin E. The water table occurs approximately 5 ft above the bedrock surface and approximately 30 ft below ground surface. The screened interval will be within the saturated, fractured clayshale unit at the top of the Denver Fm. Site EP-46 will correlate with Well 26068, which is completed in the Denver Fm. No adjacent alluvial wells exist which characterize the alluvial aquifer upgradient of Basin E.

Site EP-47

Location: Proposed well site EP-47 is located 1,750 ft north of the south line, 50 ft west of the east line, Section 27, T2S, R67W.

Rationale: Basin E (Site 26-5) downgradient water table aquifer characterization. Site EP-47 will be located in the west of Basin E to establish water quality downgradient of the basin. The water table occurs approximately 5 ft above the bedrock surface, or 25 ft below ground surface.

This well will be screened in the fractured clayshale of the uppermost Denver Fm. A well at this location will provide a control point for geology and water level fluctuations in the basin.

Site EP-48

Location: Proposed well site EP-48 is located 2,350 ft south of the north line, 1,400 ft east of the west line, Section 26, T2S, R67W.

Rationale: Basin F (Site 26-6) downgradient water table aquifer characterization. Site EP-48 will be located in Basin F along the western boundary to establish water quality below the basin. The water table occurs at the bedrock contact, or approximately 40 to 50 ft below ground surface. This well will be screened at the water table in the fractured clayshale of the uppermost Denver Fm.

Site EP-49

Location: Proposed well site is adjacent to Wells 26140, 26141, and 26142, and located 2,400 ft south of the north line, 1,500 ft west of the east line, Section 26, T2S, R67W.

Rationale: Basin F (Site 26-6) upgradient water table aquifer characterization. Site EP-49 will be located southeast of the basin boundary to establish water quality upgradient of Basin F. The water table occurs at the bedrock contact, or approximately 48 ft below ground surface. This well will be screened at the water table in the fractured clayshale of the uppermost Denver Fm. This well will correlate with Wells 26140 and 26127.

Site EP-50

Location: Proposed well site EP-50 is located 550 ft south of the north line, 800 ft east of the west line, Section 26, T2S, R67W.

Rationale: Section 26 downgradient water table and Denver aquifer characterization. This well cluster will be used to determine the vertical extent of organic and inorganic analytes downgradient of Basins A through F.

07/12/88

These wells will correlate with well clusters in Section 23 (23179, 23180, 23181; 23185, 23186, 23187; 23191, 23192, 23193) and will supplement Wells 26145, 26146, and 26147 which are of questionable construction.

The water table occurs approximately 40 ft below ground surface near the alluvium/bedrock contact. The alluvial well will be screened below the water table in the fractured clayshale at the top of the Denver Fm. Based on the log for bore number 1137, the lower sand occurs between 85 to 105 ft. A lower zone will also be screened to determine the vertical extent of contamination. Total depth of this well will not exceed 150 ft.

Site EP-52

Location: Proposed well site EP-52 is located 900 ft south of the north line, 1,700 ft west of the east line, Section 26, T2S, R67W.

Rationale: Section 26 alluvial and Denver aquifer characterization. The cluster will provide the hydrologic and water quality data to characterize and define contaminant migration out of Basin F toward the NBCS. In addition, the site will provide geologic information regarding the subsurface structure in the area. Existing wells in the area are of undocumented construction and further necessitate the installation of the well cluster.

Site EP-59

Locations: Proposed well site EP-59 is located 2,100 ft north of the south line, 2,000 ft east of the west line, Section 26, T2S, R67W.

Rationale: Basin C (Site 26-3) downgradient water table aquifer characterization. Site EP-59 will be located in the northwest portion of Basin C to establish water quality downgradient of the basin. The water table occurs at or slightly above the bedrock surface, or approximately 33 ft below ground surface. This well will be screened in the fractured clayshale of the upper Denver Fm.

5.0 TASK 21

5.1 OBJECTIVES

Phase I soils data from borings in Sections 25 and 30 indicate the presence of above background levels of arsenic (up to 50 ppm) in the soil. Arsenic has not been found in ground water in existing wells in this area in either the alluvial or the Denver aquifers at the present time or during past studies.

Few wells exist in the eastern half of Section 25 or throughout Section 30. For this reason, the paleotopographic surface of the bedrock and the thickness of the saturated alluvium are not clearly defined. Several bedrock channels have been hypothesized throughout these sections; however, their exact locations are not clearly delineated. The elevation of the water table throughout this area and how the water table interacts with First Creek are also unclear at this time.

The proposed plan for installation of piezometer nests and monitoring wells in Sections 25 and 30 has several objectives derived from Task 14. These objectives can be briefly stated as:

- o Determining the impact of high arsenic values detected within soil borings in the eastern half of Section 25 on ground water quality;
- o Defining the paleotopographic surface of the bedrock, the geology, and the hydrology in the vicinity of First Creek; and
- o Installing a piezometer nest and recorder to determine alluvial aquifer vertical hydraulic gradients in the vicinity of the Section 30 surface water gaging station on First Creek.

All of these objectives support the upcoming effort to combine and correlate soil and ground water data already obtained. Monitoring wells have been sited based on the Phase I boring program and an analysis of hydrologic and geologic data. The piezometer wells will be carefully placed to investigate the interactions between ground water and First Creek, and to complement data collected from existing and proposed monitoring wells.

07/12/88

The well installation program consists of a total of six sites including five individual monitoring wells and one piezometer nest. All of these wells are intended to augment the regional ground water monitoring network. The purpose and justification for the five regional monitoring wells and the piezometer nest are summarized below.

5.2 PROPOSED LOCATIONS

Site EP-29

Location: Proposed well site EP-29 is located 1,100 ft west of east line, 1,200 ft south of north line in Section 25, T2S, R67W.

Rationale: Alluvial aquifer characterization. Site EP-29 will be located to delineate the extent of the bedrock valley seen in the wells along the southern edge of Section 36. Bedrock in this area is anticipated to occur 40 ft below ground surface and to be covered by 10 ft of saturated alluvium.

Site EP-30

Location: Proposed well site EP-30 is located 2,000 ft north of the south line, 1,300 ft west of the east line in Section 25, T2S, R67W.

Rationale: Alluvial aquifer characterization. Site EP-30 will be located along the deep drainage ditch from North Plants to First Creek. The purposes of this well include determining the impact of high arsenic values found in surrounding soils bores and confirming the elevation of the bedrock paleotopographic surface. Based on Well 25007 (Bore 827), bedrock in this area occurs 40 ft below ground surface and is overlain by 10 ft of saturated alluvium.

Site EP-31

Location: Proposed well site EP-31 is located 2,200 ft south of the north line, 100 ft east of the west line in Section 30, T2S, R67W.

Rationale: Alluvial aquifer characterization. Water level measurements from this well will be correlated with data from Sites EP-32, EP-33, and

07/12/88

EP-34 to determine vertical hydraulic gradients near First Creek. Bedrock in this area is anticipated to occur 15 ft below ground surface and to be overlain by 8 ft of saturated alluvium.

Site EP-32

Location: Proposed well site EP-32 is located 2,100 ft south of north line, 300 ft east of west line in Section 30, T2S, R66W.

Rationale: Data from Site EP-32 will help to characterize vertical hydraulic gradients in the alluvium and upper Denver Fm. Bedrock in this area is anticipated to occur 15 ft below ground surface. The water table should occur within 5 ft of ground surface in this area. Two piezometers will be located in the saturated alluvium. The upper piezometer will be located in the top half of the saturated zone with the lower piezometer in the bottom half of the zone. A third piezometer will be installed within the upper sand of the Denver Fm. Based on the bore log for Well 30001, the top of the upper sand occurs 20 ft below ground surface. Water level measurements from the piezometer nest will be correlated with data from sites EP-31, EP-33, and EP-34, and with data from the surface water gaging station to determine the vertical hydraulic gradient.

Site EP-33

Location: Proposed well site EP-33 is located 2,100 ft south of the north line, 200 ft east of the west line in Section, 30 T2S, R66W.

Rationale: Alluvial aquifer characterization. This will be a small diameter well for water level determination. Water level measurements from this well will be correlated with data from sites EP-31, EP-32, and EP-34 to determine vertical hydraulic gradients near First Creek. Bedrock in this area is anticipated to occur 15 ft below ground surface. The water table should occur within 5 ft of ground surface due to the well's proximity to First Creek.

07/12/88

Site EP-34

Location: Proposed well site EP-34 is located 2,050 ft south of the north line, 450 east of the west line in Section 30, T2S, R66W.

Rationale: Alluvial aquifer characterization. Water level measurements from this well will be correlated with data from sites EP-31, EP-32, and EP-33 to determine vertical hydraulic gradients near First Creek. Bedrock in this area is anticipated to occur 15 ft below ground surface. The water should occur within 5 ft of ground surface.

6.0 TASK 22

6.1 OBJECTIVES

The objective of the Phase II surveys is to accurately define the degree and geometry of potential contamination found present during the Phase I surveys conducted under Task 15.

One well is proposed for the Phase II survey at Site 5-2. One boring will be drilled to bedrock and completed as an alluvial monitoring well.

6.2 PROPOSED LOCATION

Location: Site 5-2, northwest quarter of Section 5, approximately 2,400 ft south of the north section line (December Seventh Avenue) and 150 ft east of the west section line ("F" Street). One alluvial well.

Rationale: The proposed well will provide data to better define the geology and water quality in this area, and help determine whether the source site is contaminating the ground water.

7.0 TASK 25

7.1 OBJECTIVES

Ground-water hydrology and contamination in the areas of the boundary containment systems have been monitored since the late 1970's. Much of the early monitoring was conducted to investigate the contamination problems and to collect design criteria for the boundary containment systems. Following construction and start-up of the NBCS in 1982 and the NWBCS in 1984, formal ground-water monitoring programs were established utilizing monitoring wells that had been installed through the investigative projects. The monitoring programs for both systems required water quality and water level data acquisition and evaluation on a routine basis.

Task 25 continues these earlier efforts and is designed to satisfy the following objectives:

- o Monitor ground-water flow and contaminant transport in and around the boundary containment systems;
- o To define contaminant pathways; and
- o To provide water quality and hydrologic data for the operations of the systems.

In an effort to comprehensively fulfill these task objectives, the need for additional ground-water wells was recognized.

7.2 PROPOSED LOCATIONS

SITE E-55

Location: Proposed well site E-55 is located offpost and downgradient of and within the paleochannel treated by the NWBCS. The approximate location is 1,600 ft east of the west section line and 2,700 ft south of the north section line of Section 22, T2S, R67W.

07/12/88

Rationale: Proposed well site E-55 will aid in the evaluation and location of the Northwest Boundary paleochannel, in mapping bedrock geology, and in preparing water table contour maps. E-55 is also proposed to evaluate the operation of the NWBCS and water quality in the offpost area between the containment system and the proposed wells of South Adams County Water and Sanitation District (SACWSD).

SITE E-66

Location: Proposed well site E-66 is located offpost adjacent to Well 37332 along State Route 2. The approximate location is 2,400 ft east of the west section line and 2,200 ft north of the south section line of Section 22, T2S, R67W.

Rationale: Proposed well site E-66 will replace Well 36332. The existing well does not screen the entire saturated alluvium. The proposed well will be screened across the top of the water table down to the bedrock contact and provide hydrologic and water quality data offpost and downgradient of the NWBCS to monitor the performance and operation of the system.

SITE E-67

Location: Proposed well site E-67 is located offpost adjacent to Well 37334 along Yosemite. The approximate location is 30 ft west of the east section line and 2,500 ft north of the south section line of Section 21, T2S, R67W.

Rationale: Proposed well site E-67 will replace existing Well 37334. The existing well does not screen the entire saturated alluvium. The proposed well will be screened across the top of the water table down to the bedrock contact. This well will provide hydrologic and water quality data offpost and downgradient of the NWBCS in an area where contamination has recently been detected.

SITE E-68

Location: Proposed well site E-68 is located offpost adjacent to Well 37330 along State Route 2. The approximate location is 1,300 ft east of the west section line and 800 ft north of the south section line of Section 22, T2S, R67W.

Rationale: Proposed well site E-68 will replace existing Well 37330. The existing well does not screen the entire saturated alluvium. The proposed well will be screened across the top of the water table and down to the bedrock contact. This well will provide hydrologic and water quality data offpost and downgradient of the NWBCS to monitor its performance and operation.

SITE EP-01

Location: Proposed well site EP-01 is located upgradient of the NWBCS. The approximate location is 2,500 ft east of the west section line and 100 ft north of the south section line of Section 22, T2S, R67W.

Rationale: EP-01 is a proposed new well to replace existing Well 22008. Existing Well 22008 does not fully penetrate the entire thickness of the saturated alluvium. The proposed well will be screened across the top of the water table down to the bedrock contact and will consequently provide both hydrologic and water quality data for the entire zone of interest. Additionally, the proposed well will aid in the monitoring and definition of contaminant flow paths in the southern portion of the NWBCS in an area of a possible bedrock paleochannel.

SITE EP-01A

Location: Proposed well site EP-01A is located upgradient of the NWBCS. The approximate location is 450 ft north of the south section line and 2,600 ft east of the west section line of Section 22, T2S, R67W.

Rationale: Proposed well site EP-01A will provide hydrologic and water quality data to further delineate contaminant flow paths and plume definition in the southern portion of the NWBCS. Evaluation of the bedrock geology in the area indicate the presence of a possible paleochannel. Additional information derived from an evaluation of existing wells in the area (Task 25 and Task 4 Technical Plans) indicate these wells to be largely of undocumented construction.

SITE EP-02

Location: Proposed well site EP-02 is located between existing Wells 27005 and 27006. The approximate location is 750 ft east of the west section line and 850 ft south of the north section line of Section 27, T2S, R67W.

Rationale: Proposed well site EP-02 will provide hydrologic and water quality data to evaluate water quality exiting RMA south of the NWBCS. The proposed well will monitor the area to ensure that contamination does not migrate around the system. Existing wells in the area are largely of undocumented construction and past evaluations (Task 25 and Task 4 Technical Plans) indicate that the wells do not screen the entire thickness of saturated alluvium.

SITE EP-03

Location: Proposed well site EP-03 is located between existing Wells 27010 and 27011. The approximate location is 1,300 ft east of the west section line and 250 ft south of the north section line of Section 27, T2S, R67W.

Rationale: Proposed well site EP-03 will provide hydrologic and water quality data to evaluate water quality exiting RMA south of the NWBCS. The proposed well will monitor the area to ensure that contamination does not migrate around the system. Existing wells in the area are largely of undocumented construction and past evaluations (Task 25 and Task 4 Technical Plans) indicate that the wells do not screen the entire thickness of saturated alluvium.

SITE EP-04

Location: Proposed well site EP-04 will replace existing Well 23160. The approximate location is 25 ft west of the east section line and 1,700 ft south of the north section line in Section 22, T2S, R67W.

Rationale: Proposed well site EP-04 will provide the hydrologic and water quality data to better define contaminant transport in the center portion of the plume treated by the NBCS. An evaluation of existing Well 23160 indicates that it does not fully screen the entire thickness of saturated alluvium. Proposed well site EP-04 will be screened across the interval

from the top of the water table to the bedrock contact and consequently provide data which will fully characterize contaminant transport at the plume center.

SITE EP-05

Location: Proposed well site EP-05 will replace existing Well 23013. The approximate location is 1,800 ft west of the east section line and 2,800 ft north of the south section line of Section 23, T2S, R67W.

Rationale: Proposed well site EP-05 will provide the hydrologic and water quality data to better delineate the lateral contaminant extent of the plume treated by the NBCS. An evaluation of existing Well 23013 indicates that it does not fully screen the entire thickness of saturated alluvium. Proposed well site EP-05 will be screened across the interval from the top of the water table to the bedrock contact and consequently provide data which will aid in the lateral definition of the plume.

EP-06

Location: Proposed well site EP-06 will replace existing Well 23106. The approximate location is 500 ft west of the east section line and 1,450 ft north of the south section line of Section 23, T2S, R67W.

Rationale: Proposed well site EP-06 will provide the hydrologic and water quality data to better define lateral contaminant distribution in the plume treated by the NBCS. An evaluation of existing Well 23106 indicates that it does not fully screen the entire thickness of saturated alluvium. Proposed well site EP-06 will be screened across the interval from the top of the water table to the bedrock contact and consequently provide data which will aid in delineation of contaminant distribution across the plume.

EP-07

Location: Proposed well site EP-07 will replace existing well site 24162. The approximate location is 700 ft east of the west section line and 100 ft south of the north section line in Section 24, T2S, R67W.

Rationale: Proposed well site EP-07 will provide hydrologic and water quality data downgradient of the NBCS. Existing Well 24162 does not screen the entire thickness of saturated alluvium. Proposed well site EP-07 will be screened across the interval from the top of the water table to the bedrock contact and provide data for the entire zone of interest.

SITE EP-08

Location: Proposed new well site EP-08 will replace existing Well 24180. The approximate location is 1,800 ft east of the west section line and 500 ft south of the north section line of Section 24, T2S, R67W.

Rationale: Proposed new well site EP-08 will provide hydrologic and water quality data immediately upgradient of the NBCS slurry wall. Existing Well 24180 does not fully screen the entire thickness of saturated alluvium. The new well will be screened across the water table and down to the bedrock contact and provide data for the entire zone of interest.

SITE EP-09

Location: Proposed new well site EP-09 will replace existing Well 24181. The approximate location is 2,050 ft east of the west section line and 500 ft south of the north section line of Section 24, T2S, R67W.

Rationale: Proposed new well site EP-09 will provide hydrologic and water quality data immediately upgradient of the NBCS slurry wall. Existing Well 24181 does not screen the entire thickness of alluvium. The new well will be screened across the water table and down to the bedrock contact and provide data across the entire zone of interest.

SITE EP-10

Location: Proposed new well site EP-10 will replace existing Well 24182. The approximate location is 2,750 ft west of the east section line and 550 ft south of the north section line of Section 24, T2S, R67W.

Rationale: Proposed new well EP-10 will provide hydrologic and water quality data immediately upgradient of the NBCS slurry wall. Existing Well 24182 does not screen the entire thickness of alluvium. The new well will

be screened across the water table and down to the bedrock contact and provide data across the entire zone of interest.

SITE EP-11

Location: Proposed well site EP-11 will replace existing Well 24115. The approximate location is 1,850 ft east of the west section line and 1,500 ft south of the north section line of Section 24, T2S, R67W.

Rationale: Proposed new well EP-11 will provide hydrologic and water quality data upgradient of the NBCS dewatering wells. Existing Well 24115 does not screen the entire thickness of saturated alluvium. The new well will be screened across the water table and down to the bedrock contact and will provide data across the entire zone of interest.

SITE EP-12

Location: Proposed new well site EP-12 will replace existing Well 24106. The approximate location is 1,300 ft west of the east section line and 1,500 ft south of the north section line of Section 24, T2S, R67W.

Rationale: Proposed new well EP-12 will provide hydrologic and water quality data upgradient and east of the NBCS to aid in the definition of the lateral extent of contaminant migration. Existing Well 24106 does not screen the entire thickness of saturated alluvium. The new well will be screened across the water table and down to the bedrock contact and provide data across the entire zone of interest.

SITE EP-13

Location: Proposed new well site EP-13 will replace existing Well 24113. The approximate location is 1,100 ft east of the west section line and 2,000 ft south of the north section line of Section 24, T2S, R67W.

Rationale: Proposed new well EP-13 will provide hydrologic and water quality data upgradient of the plume treated by the NBCS and augment plume characterization. Existing Well 24113 does not screen the entire thickness of the alluvium. The new well will be screened across the water table and

down to the bedrock contact and provide data across the entire zone of interest.

SITE EP-14

Location: Proposed new well site EP-14 will replace existing Well 24008. The approximate location is 400 ft east of the west section line and 2,300 ft south of the north section line of Section 24, T2S, R67W.

Rationale: Proposed new well EP-14 will provide hydrologic and water quality data upgradient of the NBCS to augment plume characterization and definition. Existing Well 24008 does not screen the entire thickness of saturated alluvium. The new well will be completed from above the water table down to the bedrock contact and provide data across the entire zone of interest.

Site EP-16

Location: Proposed new well site EP-16 will replace existing Well 24010. The approximate location is 400 ft east of the west section line and 1,100 ft north of the south section line of Section 24, R2S, R67W.

Rationale: Proposed new well EP-16 will provide hydrologic and water quality data for the contaminant plume between the North Plants and Basin F and the NBCS to further define and characterize it. Existing Well 24010 does not screen the entire thickness of the saturated alluvium. The new well will be screened from above the water table down to the bedrock contact and provide data across the entire zone of interest.

SITE EP-17

Location: Proposed new well site EP-17 is located downgradient of the sewage treatment plant and pond. The approximate location is 2,708 ft east of the west section line and 2,000 ft south of the north section line of Section 24, T2S, R67W.

Rationale: Proposed well site EP-17 will define and delineate any possible contamination originating from the sewage treatment plant and lagoon, and/or North Plants to the NBCS. There are no existing wells in the vicinity. The

07/12/88

closest upgradient wells are located over 1,100 ft away and downgradient wells within 900 ft of this site are of largely undocumented construction. The proposed well will be screened from above the water table down to the bedrock surface.

SITE EP-18

Location: Proposed well site EP-18 is located downgradient of the North Plants and upgradient of the NBCS. The approximate location is 2,000 ft west of the east section line and 1,400 ft north of the south section line of Section 24, T2S, R67W.

Rationale: The proposed well site will fill in a gap in the existing monitoring network as there are no existing wells in the vicinity. The proposed well will provide hydrologic and water quality data to augment contaminant characterization and plume delineation along migration pathways originating from the North Plants. Subsurface evaluation indicates a possible paleochannel in the area. Wells located upgradient between this site and the North Plants are largely of undocumented construction while the closest acceptable downgradient well is over 1,000 ft away. The well will be screened from above the water table down to the bedrock surface.

SITE EP-23

Location: Proposed well site EP-23 is located upgradient of the North Boundary Pilot System (NBPS). The approximate location is 700 ft west of the east section line and 1,700 ft south of the north section line of Section 23, T2S, R67W.

Rationale: Proposed well site EP-23 is located upgradient of the NBPS and will provide hydrologic data to determine plume flow directions as well as water quality information for contaminant characterization. In addition, wells within 500 ft of the site are of undocumented construction. The proposed well will be screened from above the water table down to the bedrock contact.

8.0 TASK 26

8.1 OBJECTIVES

The objectives of Task 26 were to evaluate the ground-water flow systems in the South Plants, Basin A, and Basin A Neck region; to identify areas in this region for implementing IRAs, and, to prepare an assessment of alternatives for the design and construction of an alluvial ground-water intercept and treatment system in the Basin A Neck area.

The focus of the task has been revised twice. Originally a feasibility study evaluating the ground-water flow systems and developing conceptual ground-water collection and treatment systems for the South Plants and Basin A areas, the task was changed to an Alternatives Assessment for an IRA in the Basin A Neck area. The focus of the task was to evaluate appropriate alternatives for a ground-water intercept and treatment system, to select the most cost effective alternative for attaining the objective of the IRA, and to identify additional data required to design and implement the IRA.

8.2 PROPOSED LOCATIONS

Site S-1

Location: Proposed well S-1 is located 400 ft north of the south line and 1,900 ft west of the east line of Section 35, T2S, R67W.

Rationale: Well S-1 will be installed in the Denver aquifer as an addition to an existing well cluster consisting of Wells 35052, 35053, and 35054. This well will aid in defining the sand channel located west of Basin A.

Site S-2, 3, 4

Location: Well S-2, 3, 4 is located 1,200 ft south of the north line and 2,400 ft west of the east line of Section 35, T2S, R67W.

Rationale: The wells will be installed in the Basin A neck area into the various Denver sands in the region and will aid in determining the

interaction between the various units. The wells will also assist in identifying the existence and location of the inactive fault zone.

Site S-5, 6, 7, 8

Location: Site 3-5, 6, 7, 8 is located 400 ft south of the north line and 1,200 ft west of the east line of Section 35, T2S, R67W.

Rationale: Wells S-5, S-6, S-7, and S-8 will be installed as a cluster along the fault northwest of Basin A Neck. This location is approximately on the axis of the Basin A Neck. The wells will penetrate the alluvium and the three major Denver sands found beneath the site. These wells will help describe the influence of the inactive fault on ground-water flow. They will also allow chemical characterization of the respective alluvial and Denver units.

Site S-9, 10, 11

Location: Site S-9, 10, 11 is located 2,100 ft north of the south line and 300 ft east of the west line of Section 35, T2S, R67W.

Rationale: A cluster of wells, Wells S-9, S-10, and S-11, will be installed on the western region of Basin A where it is suspected that the Upper Denver sand unit subcrops and is in contact with the alluvium. Well S-9 will be installed in the alluvium, Well S-10 in the subcropping sand unit, and Well S-11 in a lower Denver sand unit. These wells will aid in defining the location of the Denver sand channels west of Basin A and in determining the interactions between the Denver and the alluvium.

Site S-12

Location: Site S-12 is located 100 ft north of the south line and 1,400 ft east of the west line of Section 36, T2S, R67W.

Rationale: Well S-12 will be installed in the alluvium between South Plants and Basin A to monitor the movement of ground water and contaminants towards Basin A.

Site S-13, 14

Location: Site S-3, 14 is located 300 ft north of the south line and 500 ft west of the east line of Section 35, T2S, R67W.

Rationale: Wells S-13 and S-14 will be installed next to Wells 71 and 72 immediately northwest of South Plants in Section 35. Well 71 is installed in the upper Denver sand unit and will be used to monitor a pumping test that will be conducted using Well S-13, which will also penetrate this unit. A single pair of piezometers will be installed near Well S-13. These will be installed in the Denver shale, below the water table but above the upper Denver sand. The piezometers will be used to monitor the response, if any, of the shale unit to the pump test. Well 72 is installed in the lower Denver sand unit and Well S-14 will be installed in the intermediate Denver sand unit associated with the coal seam. Environmental Science and Engineering, Inc. (ESE) has reported problems sampling this well. If these problems cannot be corrected, another well may be installed to provide chemical data and flow characteristics of the lower Denver sand unit.

Site S-15

Location: Site S-15 is located 2,000 ft north of the south line and 1,300 ft east of the west line of Section 3, T3S, R67W.

Rational: Site S-15 will be installed in the alluvium next to the lakes to provide information which will assist in an analysis of ground-water/surface water interactions.

Site S-16

Location: Site S-16 is located 800 ft north of the south line and 100 ft east of the west line of Section 1, T3S, R67W.

Rationale: Site S-16 will be installed in the alluvium next to the lakes to provide information which will assist in an analysis of ground-water/surface water interactions.

07/14/88

Site S-17

Location: Site S-17 is 1,900 ft west of the east line and 1,500 ft north of the south line of Section 1, T3S, R67W.

Rationale: Site S-17 will be installed in the alluvium next to the lakes to provide information which will assist in an analysis of ground-water/surface water interactions.

Site S-18

Location: Site S-18 is located 1,700 ft north of the south line and 800 ft west of the east line of Section 1, T3S, R67W.

Rationale: Site S-18 will be installed in the alluvium next to the lakes to provide information which will assist in an analysis of ground-water/surface water interactions.

9.0 TASK 36

9.1 OBJECTIVES

Task 36 is designed to assess the performance of the NBCS. In order to perform such an investigation, two basic objectives must be satisfied:

- o Address the potential of Denver Formation sandstones in the area of the NBCS to act as conduits for contaminant transport.
- o Determine the adequacy of the present dewatering, recharge, and soil-bentonite barrier system to effectively mitigate the migration of alluvial contamination across the RMA North Boundary.

The successful accomplishment of these task objectives (primarily the Denver sands assessment) will require the installation of additional wells in the NBCS area.

The specific sites for the task have been chosen after extensive review of the local geology and of existing hydrologic and contaminant distribution data. These sites are composed of offpost sites and onpost sites upgradient and downgradient of the soil-bentonite barrier at the North Boundary.

9.2 PROPOSED LOCATIONS

Site E-32

Location: Proposed well site E-32 is located onpost downgradient from the barrier and is 30 ft west of the east section line (D Street) and 140 ft south of the north section line (96th Avenue) in Section 23, T2S, R67W.

Rationale: Proposed well site E-32 will provide hydrologic and water quality data to assess whether first and second Denver sands are acting as contaminant migration pathways beneath the NBCS. Site E-32 is also located directly downgradient of Denver dewatering Well 23342 which is suspected of being poorly completed and may provide a mechanism for cross contamination between aquifers.

07/14/88

Site E-33

Location: Proposed well site E-33 is located onpost 175 ft south of the north line (96th Avenue) and 850 ft east of the west line (D Street) in Section 24, T2S, R67W.

Rationale: Proposed well site E-33 is located downgradient of the barrier and will provide hydrologic and water quality data in the first and second Denver sands. There are currently no functional Denver wells in this area. This well will be utilized to fill in this data gap and to assess whether these Denver units are acting as contaminant migration pathways.

Site E-34

Location: Proposed well site E-34 is located at existing alluvial Well 37338 offpost on the north side of 96th Avenue about 2,500 ft east of the west line (Peoria Street) and 20 ft north of the south line (96th Avenue) in Section 13, T2S, R67W.

Rationale: Proposed well site E-34 has been chosen to obtain hydrologic and water quality data in the first and second Denver sands downgradient of the NBCS. There are currently no first or second Denver sands water quality wells in service in this area. Water quality data is needed here to assess if these Denver units are acting as contamination pathways beneath the NBCS.

Site E-39

Location: Proposed well site E-39 is located 600 ft north of the south line (96th Avenue) and 2,675 ft east of the west line (Havana Street) in Section 14, T2S, R67W.

Rationale: Proposed well site E-39 will provide important geologic data in the assessment of the lateral and northerly extent of the first and second Denver sands. This site is located downgradient of where the first sand is suspected to subcrop and discharge into the alluvium. There are presently no first or second Denver sands wells in this area and monitoring wells in these sand units are required to assess the water quality of the Denver sands downgradient of the barrier at this location.

Site E-40

Location: Proposed well E-40 is at the location of existing Well 37305 and is located 1,800 ft west of the east line (Peoria Street) and 1,300 ft north of the south line (96th Avenue) in Section 14, T2S, R67W.

Rationale: Proposed well site E-40 will be a cluster site to assess the hydrologic and water quality data in the alluvium and first and second Denver sands downgradient of the NBCS. This alluvial site has been chosen at the location of the projected subcrop and discharge point of a Denver sandstone unit to assess the water quality. The first and second Denver wells will be utilized to assess whether these units are acting as contaminant migration pathways which bypass the NBCS.

Site E-41

Location: Proposed well site E-41 is located 1,360 ft west of the east line (Peoria Street) and 1,800 ft north of the south line (96th Avenue) in Section 14, T2S, R67W.

Rationale: Proposed well site E-41 will be a cluster site downgradient of the NBCS. This alluvial site has been specifically chosen to assess the water quality downgradient of where a Denver sandstone unit is suspected to subcrop and discharge into the alluvium. In addition, this well will provide hydrologic and water quality data to assess whether the first and second Denver sands are transporting contaminants.

Site E-42

Location: Proposed well site E-42 is approximately 380 ft west of the east line (Peoria Street) and 820 ft north of the south line (96th Avenue) of Section 14 T2S, R67W.

Rationale: Proposed well site E-42 will provide hydrologic and water quality data in the alluvium and first and second Denver sands downgradient of the NBCS. This site has been chosen upgradient of the suspected subcrop of a Denver sandstone unit and will help define the geology of the area.

07/12/88

Site E-63

Location: Proposed well site E-63 is located 1,000 ft east of the west line (Peoria Street) and 900 ft north of the south line (96th Avenue) of Section 13, T2S, R67W.

Rationale: Proposed well site E-63 will provide geologic, water quality, and water level data to assess whether the alluvium and first and second Denver sands are contaminated at this site downgradient of the NBCS. Specifically, the alluvial well at this site will assess water quality downgradient of a suspected subcrop and discharge point of a Denver sandstone unit.

Site E-69

Location: Proposed well site E-69 is located 230 ft north of the south line (96th Avenue) and 1,260 ft west of the east line (Peoria Street) of Section 14, T2S, R67W.

Rationale: Proposed well site E-69 will be a corehole to characterize the geology. The owner at this site did not wish to have permanent wells on his property, but was cooperative in allowing permission to drill a boring and gather geologic information. The site will be specifically utilized to define the first Denver sand just upgradient from where it is suspected to subcrop.

Site EP-19

Location: Proposed onpost downgradient well site EP-19 is located 1,780 ft west of the east line (D Street) and 210 ft south of the north line (96th Avenue) in Section 23, T2S, R67W. The site is some 160 ft north of existing Well 23436.

Rationale: Proposed well site EP-19 will provide geologic, water quality, and water level data in the alluvium and first and second Denver sands downgradient of the NBCS. An alluvial well has been proposed here to fill in a data gap in the area and also to assess the water quality and the location of a suspected subcrop and discharge point of a Denver sandstone unit. The first and second Denver sandstone wells will provide water

quality and water level data downgradient from wells located in the same sandstone unit, but closer to the soil-bentonite barrier.

Site EP-20

Location: Proposed onpost downgradient well site EP-20 is located 1,100 ft west of the east line (D Street) and 140 ft south of the north line (96th Avenue) in Section 23, T2S, R67W.

Rationale: Proposed well site EP-20 will provide geologic, water quality, and water level information in the alluvium and first and second Denver sands downgradient of the soil-bentonite barrier. The alluvial well will assess the water quality just downgradient from where a Denver sandstone unit is suspected to subcrop. The first sandstone well is required to assess water quality and water levels downgradient from Well 23202 which is located in the same sandstone unit, but closer to the soil-bentonite barrier. The second sandstone well will help characterize the configuration of the sandstone unit as well as provide water quality and water level data.

Site EP-21

Location: Proposed onpost downgradient well site EP-21 is located 650 ft west of the east line (D Street) and 130 ft south of the north line (96th Avenue) in Section 23, T2S, R67W.

Rationale: Proposed well site EP-21 will provide geologic, water quality, and water level data in the alluvium and first and second Denver sands downgradient of the NBCS. The alluvial well will provide data to assess the water quality just downgradient of where a Denver sandstone unit is suspected to subcrop into the alluvium. The first sandstone well is required to assess water quality and water levels downgradient from wells located in the same sandstone unit that are closer to the soil-bentonite barrier. From work done by ESE, this sand unit appears to be a major channel sand that goes under the soil-bentonite barrier. A second Denver sand well at this site will characterize the configuration of the sand unit and also provide water quality and water level data.

Site EP-22

Location: Proposed onpost downgradient well site EP-22 is located 1,950 ft west of the east line (D Street) and 220 ft south of the north line (96th Avenue) in Section 24, T2S, R67W.

Rationale: Proposed well site EP-22 will provide geologic, water quality, and water level data in the alluvium and first and second Denver sands. Currently, there are no Denver wells downgradient of the soil-bentonite barrier at this location.

Site EP-25

Location: Proposed onpost downgradient well site EP-25 is located 850 ft west of the east line (D Street) and 900 ft south of the north line (96th Avenue) in Section 23, T2S, R67W.

Rationale: Proposed well site EP-25 will provide geologic, water quality, and water level data in the first Denver sand upgradient of the NBCS. This site has been chosen to better define the eastern lateral extent of the channel sand which is mentioned under site EP-21. This well will help to determine points of entry for contaminants into this unit.

Site EP-26

Location: Proposed onpost downgradient well site EP-26 is located 210 ft west of the east line (D Street) and 1,700 ft south of the north line (96th Avenue) in Section 23, T2S, R67W.

Rationale: Proposed well site EP-26 will provide geologic, water quality, and water level data in the first Denver sand upgradient of the NBCS. This site was chosen to better define the western lateral extent of the channel sand which appears to continue under the soil-bentonite barrier and points of entry for contaminants into this unit.

Site EP-27

Location: Proposed onpost downgradient well site EP-27 is located 710 ft west of the east line (D Street) and 1,130 ft south of the north line (96th Avenue) in Section 23, T2S, R67W.

Rationale: Proposed well site EP-27 will provide geologic, water quality, and water level data in a major first Denver sandstone unit upgradient of the NBCS. This proposed well has been placed directly in the center of the suspected channel sand and will assist in determining points of entry for contamination into this unit.

Site EP-28

Location: Proposed onpost downgradient well site EP-28 is located 2,480 ft west of the east line (D Street) and 235 ft south of the north line (96th Avenue) in Section 23, T2S, R67W.

Rationale: Proposed well site EP-28 will provide geologic, water quality, and water level data in the alluvium and first Denver sand. The alluvial well will be utilized to assess the water quality just downgradient of a suspected subcrop of a Denver sand unit. The first Denver sand well will help characterize the water quality and the extent of the first sandstone in this downgradient area.

Site EP-76

Location: Proposed well site EP-76 is located approximately 200 ft south of the north section line and 505 ft west of the east section line of Section 23 (T2S, R67W).

Rationale: Provide geologic data for stratigraphic correlations.

10.0 TASK 38

10.1 OBJECTIVES

The objectives of Task 38 are as follows:

- o Determine the source(s) of TCE in ground water in the Western Tier;
- o For such source(s), define the contaminant plume between the source and the RMA boundary; and
- o Obtain all other data necessary for the Army, in consultation with U.S. Environmental Protection Agency (EPA), Colorado, and Shell, to determine appropriate removal or final remedial action to be taken with respect to the TCE source and/or the TCE plume of contamination.

These objectives are accomplished through the conduct of a remedial investigation and preliminary remedial alternatives assessment. The remedial investigation includes a detailed review of historical records, personal interviews, geophysics studies, soil gas studies, soil borings and analysis, well installation, ground-water sampling and analysis, and building (sumps, drains, etc.) sampling and analysis.

Ground-water monitoring wells will be installed and sampled to assess the degree and extent of ground-water contamination in the Western Tier. It is the intent of this study to verify the presence of contaminant sources and to determine whether migration of contaminants has occurred which may be contributing to low levels of contaminants measured in nearby SACWSD water supply wells.

Studies of the DBCP plume in Section 33 indicate that contaminant plumes will be narrow in the Western Tier. Wells must be placed in the centerline of the plume in order to accurately track contaminant movement. The present monitoring well network does not appear to adequately define TCE migration in the Western Tier area. Data from the new wells together with information collected from the present monitoring well network will help to further define the local ground-water flow system and the limits of contamination.

07/13/88

A total of 22 ground-water monitoring wells or well clusters are expected to be installed and sampled to assess the degree and extent of ground-water contamination in the Western Tier. Note that locations are tentative. Exact locations will be determined based upon information obtained during the study.

These wells will provide data for the evaluation of ground water at the sites. Wells are also planned for the far western border of RMA where ground-water data are sparse. Analyses of samples from these wells are expected to define whether contaminants are migrating from the eastern side of Section 4 to the far western borders of Sections 4 and 33. Four wells/well clusters are planned for sites in Section 9. At least one well will be installed in the middle of a bedrock valley in the northwestern corner of Section 33, a valley which is to be mapped by geophysical methods. The SACWSD wells are located in this bedrock valley. Other wells will be located following further analysis of geophysical and hydrological data.

10.2 PROPOSED LOCATIONS

Site WT33-1

Location: Proposed well site WT33-1 is in the northwest quarter of Section 33, approximately 900 ft east of the west section line and 2,700 ft north of the south section line (December Seventh Avenue). One alluvial well is proposed for this site.

Rationale: Proposed well site WT33-1 was located to provide water quality data between a mapped TCE soil gas plume in the center of Section 33 and the contaminated SACWSD well on the northwest side of Section 33.

Site WT33-2

Location: Proposed well site WT33-2 is in the northwest quarter of Section 33, approximately 1,200 ft east of the west section line and 2,950 ft north of the south section line (December Seventh Avenue). Three nested alluvial wells are proposed for this site each screening a maximum of 20 ft of the aquifer.

Rationale: Proposed well site WT33-2 will provide geologic, water quality, and water level data for alluvium filling a bedrock channel known to be in this area.

Site WT33-3

Location: Proposed well site WT33-3 is in the southwest quarter of Section 33, approximately 2,050 ft east of the west section line and 1,050 ft north of the south section line (December Seventh Avenue). Two nested alluvial wells are proposed for this site each screening a maximum of 20 ft of the aquifer.

Rationale: Proposed well site WT33-3 was located to intercept a TCE groundwater plume mapped by the Tracer soil gas methodology, emanating from Sites 4-2 and 4-6 to the south.

Site WT4-1

Location: Proposed well site WT4-1 is in the northwest quarter of Section 4, approximately 2,000 ft east of the west section line and 50 ft south of the north section line (December Seventh Avenue). Two nested alluvial wells are proposed for this site each screening a maximum of 20 ft of the aquifer.

Rationale: Proposed well site WT4-1 was located to intercept a TCE groundwater plume mapped by the Tracer soil gas methodology, emanating from Site 4-2 to the south.

Site WT4-2

Location: Proposed well site WT4-2 is in the northeast quarter of Section 4, approximately 1,300 ft west of the east section line (B Street) and 1,000 ft south of the north section line (December Seventh Avenue), in Site 4-4. One alluvial well is proposed for this site that will screen 20 ft of the upper aquifer.

Rationale: Proposed well site WT4-2 was located to intercept a TCE groundwater plume mapped by the Tracer soil gas methodology, emanating from Site 4-6 to the south.

Site WT4-3

Location: Proposed well site WT4-3 is in the northwest quarter of Section 4, approximately 850 ft east of the west section line and 2,250 ft south of the north section line (December Seventh Avenue). Three nested alluvial wells are proposed for this site each screening a maximum of 20 ft of the aquifer.

Rationale: Proposed well site WT4-3 was located to provide geologic data on a suspected bedrock channel located on the east side of Section 4 and to provide water quality and water level data from this area.

Site WT4-4

Location: Proposed well site WT4-4 is in the western half of Section 4, approximately 2,200 ft east of the west section line and 2,600 ft south of the north section line (December Seventh Avenue). One alluvial well is proposed for this site which will screen the entire alluvial aquifer thickness estimated at 20 ft.

Rationale: Proposed well site WT4-4 was located to intercept a TCE groundwater plume mapped by the Tracer soil gas methodology, emanating from Site 4-2 to the south.

Site WT4-5

Location: Proposed well site WT4-5 is in the southwest quarter of Section 4, approximately 1,000 ft east of the west section line and 1,750 ft north of the south section line (Sixth Avenue). One alluvial well is proposed for this site which will screen the entire alluvial aquifer thickness estimated at 20 ft.

07/12/88

Rationale: Proposed well site WT4-5 was located to provide geologic data on a suspected bedrock channel located on the east side of Section 4 and to provide water quality and water level data from this area.

Sites WT4-6, WT4-7, WT4-8, WT4-9, WT4-10, and WT4-11

Location: These proposed well sites are located in Site 4-6 in the southeast corner of Section 4. Each will be completed to a maximum depth of 20 ft in the alluvial aquifer.

Rationale: These proposed well sites were located to delineate the source of TCE contamination in the ground-water as mapped by the Tracer soil gas study emanating from Site 4-6.

Site WT4-12

Location: The proposed well site WT4-12 is located in Site 4-2 in the southern half of section 4, approximately 2,800 ft east of the west section line and 850 ft north of the south section line (Sixth Avenue). One well will be completed to a maximum depth of 20 ft in the alluvial aquifer.

Rationale: The proposed well site WT4-12 was located to delineate the source of TCE contamination in the ground-water as mapped by the Tracer soil gas study to be emanating from Site 4-2.

Site WT4-13

Location: Proposed well site WT4-13 is in the southwest quarter of Section 4, approximately 1,200 ft east of the west section line and 450 ft north of the south section line (Sixth Avenue). One well will be completed to a maximum depth of 20 ft in the alluvial aquifer.

Rationale: Proposed well site WT4-13 was located to provide geologic data on a suspected bedrock channel located on the east side of Section 4 and to provide water quality and water level data from this area.

07/12/88

Site WT3-1

Location: Proposed well site WT3-1 is in the southeast quarter of Section 3, approximately 450 ft east of the west section line and 50 ft north of the south section line (Sixth Avenue). One alluvial well is proposed for this site which will screen a maximum of 20 ft of the aquifer.

Rationale: Proposed well site WT3-1 was located to monitor ground-water quality upgradient of Site 4-6 and to provide water level information.

Site WT9-1

Location: Proposed well site WT9-1 is in the northeast quarter of Section 9, approximately 1,100 ft west of the east section line and 100 ft south of the north section line (Sixth Avenue). One alluvial well is proposed for this site which will screen the entire alluvial aquifer thickness estimated at 20 ft.

Rationale: Proposed well site WT9-1 was located based on a TCE "hot spot" identified by the Petrex soil gas study.

Site WT9-2

Location: Proposed well site WT9-2 is in the northeast quarter of Section 9, approximately 2,050 ft west of the east section line and 1,650 ft south of the north section line (Sixth Avenue). Two nested alluvial wells are proposed for this site, each screening a maximum of 20 ft of the alluvial aquifer.

Rationale: Proposed well site WT9-2 was located based on a TCE "hot spot" identified by the Petrex soil gas study.

Site WT9-3

Location: Proposed well site WT9-3 is in the northeast quarter of Section 9, approximately 10 ft west of the east section line and 2,550 ft south of the north section line (Sixth Avenue). One alluvial well is proposed for this site to screen 20 ft of the aquifer.

07/12/88

Rationale: Proposed well site WT9-3 was located to provide alluvial water level and bedrock data in an area identified as a data gap.

Site WT9-4

Location: Proposed well site WT9-4 is in the southeast quarter of Section 9, approximately 1,750 ft west of the east section line and 1,250 ft north of the south section line. Two nested alluvial wells are proposed for this site, each screening a maximum of 20 ft of the alluvial aquifer.

Rationale: Proposed well site WT9-4 was located based on a TCE "hot spot" identified by the Petrex soil gas study.

Site WT9-5

Location: Proposed well site WT9-5 is in the southeast quarter of Section 9, approximately 1,650 ft west of the east section line and 100 ft north of the south section line. Two nested alluvial wells are proposed for this site, each screening a maximum of 20 ft of the alluvial aquifer.

Rationale: Proposed well site WT9-5 was located to identify any contaminated ground-water entering RMA from the south.

11.0 TASK 39

11.1 OBJECTIVES

There are two primary objectives of the proposed monitoring program. The first and most important objective of this task is to delineate suspected contaminated alluvial ground-water plumes that may be emanating from the RMA northern boundary. This will include further definition of the known contaminant plume extending northwestward from the northern boundary along the inferred First Creek paleochannel described in the Offpost Contamination Assessment Report (CAR) (ESE, 1987, RIC#87202R01). It will also include determining whether contaminant plumes extend from the RMA northern boundary to remote areas to the north of RMA where isolated detections of several organic contaminants have been documented. Any plumes that are defined in this area will be specifically delineated in enough detail to evaluate remedial action alternatives if the need for remedial actions is established.

A second objective of the offpost proposed monitoring plan is to assess the quality of ground water in Denver Fm aquifers downgradient of the RMA northern boundary. Of particular concern is whether these units are acting as contaminant migration pathways which bypass the NBCS. The data from these wells will also be used to assess to what extent, if any, ground water from the Denver Fm may be contributing to alluvial aquifer contamination. This scenario is being addressed in this study because many of the Denver Fm units subcrop and discharge into the alluvium immediately downgradient of the RMA northern boundary. However, most of the Denver Fm wells will be addressed under Task 36.

Based upon the results of geologic, hydrologic, and chemical analyses from these wells and boreholes, additional sites may be developed. These sites will be installed to provide specific data identified as being needed based on the initial group of sites. Specific locations are described in the following sections.

11.2 PROPOSED LOCATIONS

Site E-36

Location: Proposed Site E-36 is along the west side of Potomac Street approximately 20 ft west of the east line and 500 ft north of the south line in the southeast quarter, southeast quarter of Section 13. This site is for a possible cluster of one alluvial and two Denver wells.

Rationale: Proposed well site E-36 was located to provide geologic, water quality, and water level data northeast of the NBCS.

Site E-38

Location: Proposed site E-38 is a site for the installation of a possible cluster of one alluvial and two Denver wells along the west side of Highway 2, approximately 1,200 ft northeast of the intersection of East 96th Avenue. The site is 900 ft east of the west section line and 900 ft north of the south section line lying in the southwest quarter, southwest quarter of Section 14.

Rationale: Proposed well site E-38 is located to assess the configuration, extent, and water quality of Denver sand units northwest of the NBCS. This well cluster will fill a large data gap that exists in this area.

Site E-43

Proposed well site E-43 is located in 1,500 ft north of the south line and 2,650 ft east of the west line of Section 13.

Rationale: Proposed alluvial well site E-43 will provide water quality and geologic data to assess whether a well-defined alluvial channel exists in this area of Section 13, and if such a channel is acting as a primary pathway for contaminant migration to areas further north.

Site E-44

Location: Proposed well site E-44 is located approximately 1,600 ft west of the east line and 2,000 ft north of the south line of Section 14.

Rationale: Proposed well site E-44 has been located to define the documented contaminant plume that appears to be associated with the inferred First Creek paleochannel. In addition, first and second Denver sand wells will provide geologic, water quality, and water level data, to assess whether these units are contaminated at this site downgradient of the NBCS.

Site E-45

Location: Proposed well Site E-45 is along the east side of Peoria Street about 20 ft east of the west line and 2,050 ft north of the south line of Section 13 lying in the northwest quarter, southwest quarter of Section 13. This site is for a cluster of two Denver wells at the site of the existing alluvial Well 37323.

Rationale: Proposed well site E-45 will provide geologic, water quality, and water level data in the first and second Denver sands downgradient of the NBCS. There are currently no functional Denver wells in this area.

Site E-46

Location: Proposed well site E-46 is 2,600 ft north of the south line and 1,300 ft east of the west line of Section 13. There will be one alluvial and two Denver wells installed at the well site.

Rationale: Proposed well site E-46 will provide geologic, water quality, and water level data in the alluvium and first and second Denver sands downgradient of the NBCS. The alluvial well at this site will assess whether a well-defined alluvial channel exists in this area and if such a channel is acting as a primary pathway for contaminant migration to areas further north. The Denver wells will be utilized to assess the configuration, extent, and water quality of the first and second Denver sand units downgradient of the NBCS.

Site E-47

Location: Proposed well site E-47 is located 2,600 ft north of the south line and 2,550 east of the west line of Section 13.

07/12/88

Rationale: Proposed well site E-47 will provide geologic, water quality, and water level data in the alluvium and first and second Denver sands. The alluvial well at this site will be specifically utilized to assess whether a well-defined alluvial channel exists in this area and if such a channel is acting as a primary pathway for contaminant migration to areas further north. The Denver wells will provide data to assess the configuration, extent, and water quality of the first and second Denver sand units downgradient of the NBCS.

Site E-48

Location: Proposed well site E-48 is located 2,600 ft north of the south line and 1,300 west of the east line of Section 13.

Rationale: Proposed well site E-48 will provide geologic, water quality, and water level data in the alluvium downgradient of the NBCS. The purpose of this alluvial well is to assess whether a well-defined alluvial channel exists in this area and if such a channel is acting as a primary pathway for contaminant migration to areas further north.

Site E-49

Location: Proposed well site E-49 lies along the east side of Potomac Street about 2,750 ft north of the south line and 20 ft east of the west line in the northwest quarter, southeast quarter of Section 18. This site is for the installation of two Denver wells at the site of existing alluvial Well 37327.

Rationale: Proposed well site E-49 will provide geologic, water quality, and water level data in the first and second Denver sands to the northeast of the NBCS. These wells are required to assess the configuration, extent, and water quality of the first and second Denver sands at this location.

Site E-50

Location: Proposed well site E-50 is a site for the installation of one alluvial well and one optional Denver well along the west side of Highway 2. It is 3,100 ft east of the west line and 3,500 ft north of the south line of

Section 14 and lies in the southwest quarter, northeast quarter of Section 14.

Rationale: Proposed well site E-50 is required to define the documented contaminant plume that appears to be associated with the inferred First Creek paleochannel. In addition, a first Denver sand well will provide geologic, water quality, and water level data to assess whether this unit is contaminated at this location.

Site E-51

Location: Proposed well site E-51 is at the site of an existing shallow Well 37342 where an additional one or two optional Denver wells will be installed. The site is approximately 3,800 ft east of the west line and 4,200 ft north of the south line of Section 14 in the northwest quarter, northeast quarter of Section 14.

Rationale: Proposed well site E-51 will provide geologic, water quality, and water level data in the first and second Denver sands downgradient of the NBCS. These wells are required to assess the configuration, extent, and water quality of these sand units at this location.

Site E-52

Location: Proposed well site E-52 is along the northwest side of Peoria Street approximately 500 ft northeast of the intersection with East 104th Avenue. This site is in the southeast quarter, southeast quarter of Section 11, approximately 400 ft west of the east line and 400 ft north of the south line of Section 11. This site will be used for the installation of one alluvial well.

Rationale: Proposed well site E-52 will be utilized to assess the extent of alluvial ground water contamination in the vicinity of Well 37344 and the Boller Well. This zone represents an area more than a mile downgradient of the NBCS where substantial concentrations of organic contaminants have been detected.

Site E-53

Location: Proposed well site E-53 is along the north side of East 104th Avenue, approximately 900 ft east of the west line and 20 ft north of the south line in the southwest quarter, southwest quarter of Section 12. This site is for the installation of one alluvial well and two optional Denver wells.

Rationale: Proposed well site E-53 will provide geologic, water quality, and water level data in the alluvium and first and second Denver sands downgradient of the NBCS. The alluvial well will be specifically utilized to identify the extent of alluvial ground-water contamination in the vicinity of Well 37344 and the Boller Well. This zone represents an area more than a mile downgradient of the NBCS where substantial organic contaminants have been detected. The Denver wells are required to assess the configuration, extent, and water quality of the first and second Denver sands at this location.

Site E-54

Proposed well site E-54 is along the north side of East 104th Avenue, approximately 3,300 ft east of the west line and 20 ft north of the south line the southwest quarter, southeast quarter of Section 12. This site is for the installation of one alluvial well and two optional Denver wells.

Rationale: Proposed well site E-54 will provide geologic, water quality, and water level data in the alluvium and first and second Denver sands downgradient of the NBCS. The alluvial well will be specifically utilized to identify the extent of alluvial ground-water contamination in the vicinity of Well 37344 and the Boller Well. This zone represents an area more than a mile downgradient of the NBCS where substantial organic contaminants have been detected. The Denver wells are required to assess the configuration, extent, and water quality of the first and second Denver sands at this location.

07/12/88

Site E-57

Location: Proposed well site E-57 is along the north side of Highway 44 (East 104th Avenue west of the junction with Highway 2) which runs along the south line of Section 11. The site is about 3,500 ft east of the west line and 30 ft north of the south line lying in the southwest quarter, southeast quarter of Section 11. This site is for the installation of one optional alluvial well.

Rationale: Proposed well site E-57 will provide geologic, water quality, and water level data in the alluvium substantially downgradient of the NBCS. This well is required to assess the extent of alluvial contamination substantially downgradient of the NBCS and away from known areas of high contamination.

Site E-58

Location: Proposed well site E-58 is along the west side of Peoria Street, about 1,700 ft north of the south line and 20 ft west of the east line in the northeast quarter, southeast quarter of Section 11. This site is for the installation of one alluvial well.

Rationale: The proposed well site E-58 will be utilized to assess the extent of alluvial ground-water contamination in the vicinity of the "Boller Well" and Well 37344. This zone represents an area more than a mile downgradient of the NBCS where substantial concentrations of organic contaminants have been detected.

Site E-59

Location: Proposed well site E-59 lies along the northwest side Highway 2, approximately 1,900 ft east of the west line and 2,800 ft north of the south line in the southeast quarter, northwest quarter of Section 12. This installation is for one optional alluvial well.

Rationale: Proposed well site E-59 will provide geologic, water quality, and water level data in the alluvium downgradient of the NWBCS. This well

07/12/88

is required to assess the extent of alluvial contamination downgradient of the NBCS and away from known areas of high contamination.

Site E-60

The proposed well site E-60 is 50 ft east of the west line and 2,600 ft north of the south line in the northwest corner of the southwest corner of Section 15.

Rationale: Proposed well site E-60 will provide geologic, water quality, and water level data in the alluvium downgradient of the NWBCS. This well is required to assess the extent of alluvial contamination downgradient of the NWBCS and away from known areas of high contamination.

Site E-61

Location: Proposed well site E-61 is along the north side of Highway 44, approximately 100 ft east of the west line and 30 ft north of the south line in the southwest quarter, southwest quarter of Section 11. This site is for the installation of one optional alluvial well.

Rationale: Proposed well site E-61 will provide geologic, water quality, and water level data in the alluvium substantially downgradient of the NBCS. This well is required to assess the extent of alluvial contamination substantially downgradient of the NBCS and away from known areas of high contamination.

Site E-62

Location: Proposed well site E-62 is located in the center of Section 11, approximately 2,600 ft south of the north line and 2,600 ft east of the west line of Section 11.

Rationale: Proposed well site E-62 will provide geologic, water quality, and water level data in the alluvium substantially downgradient of the NBCS. This well is required to assess the extent of alluvial contamination substantially downgradient of the NBCS and away from known areas of high contamination.

07/13/88

Site E-64

Location: Proposed well site E-64 is along the east side of Peoria Street, approximately 4,000 ft north of the south line and 20 ft east of the west line of Section 13.

Rationale: Proposed well site E-64 will provide geologic, water quality, and water level data in the alluvium and first and second Denver sands downgradient of the NBCS. The alluvial well at this site will assess whether a well-defined alluvial channel exists in this area and if such a channel is acting as a primary pathway for contaminant migration to areas further north. The Denver wells will be utilized to assess the configuration, extent, and water quality of the first and second Denver sand units downgradient of the NBCS.

Site E-65

Location: Proposed well site E-65 is located approximately 1,000 ft east of Highway 2. The site is 2,800 ft west of Peoria Street (the line dividing Section 13 and 14) and 1,700 ft north of 96th Avenue (the RMA north boundary) on private land.

Rationale: Proposed well site E-65 will provide geologic water quality and water level data in the alluvium and first and second Denver sands downgradient of the NBCS. This cluster site will fill a large data gap and aid in the assessment of offpost contaminant migration.

Site E-70

Location: Proposed well site E-70 is just off of Peoria Street, 550 ft north of 96th Avenue.

Rationale: Proposed well site E-70 is a replacement for Well 37308 which has no construction documentation. This alluvial well is needed to fill in a data gap in water levels and water quality.

Site E-71

Location: Proposed well site E-71 is located 50 ft east of Peoria Street and 1,300 ft north of 96th Avenue.

Rationale: Proposed well site E-71 is a replacement for Well 37309 which has no construction documentation. This alluvial well is needed to fill in a data gap in water levels and water quality.

Site E-72

Location: Proposed well site E-72 is located 2,400 ft north of 96th Avenue and just east of Highway 2.

Rationale: Proposed well site E-72 is a replacement for Well 37313. This alluvial well is needed to fill in a data gap in water levels and water quality.

Site E-73

Location: Proposed well site E-73 is located 690 ft east of Peoria Street and approximately 2,600 ft north of 96th Avenue on private land.

Rationale: Proposed well site E-73 will provide geologic, water quality, and water level data in the alluvium and first and second Denver sands downgradient of the NBCS. The alluvial well at this site will assess whether a well-defined alluvial channel exists in this area and if such a channel is acting as a primary pathway for contaminant migration to areas further north. The Denver wells will be utilized to assess the configuration, extent, and water quality of the first and second Denver sand units downgradient of the NBCS.

Site E-74

Location: Proposed well site E-74 is located 1,900 ft east of Peoria Street and approximately 2,600 ft north of 96th Avenue.

Rationale: Proposed well site E-74 will provide geologic water quality and water level data in the alluvium and first and second Denver sands

downgradient of the NBCS. The alluvial well at this site will assess whether a well-defined alluvial channel exists in this area and if such a channel is acting as a primary pathway for contaminant migration to areas further north. The Denver wells will be utilized to assess the configuration, extent, and water quality of the first and second Denver sand units downgradient of the NBCS.

Site E-75

Location: Proposed well site E-75 is located along East 104th Avenue, 300 ft east of Peoria Street.

Rationale: Proposed well site E-75 will be utilized to assess the extent of alluvial ground water contamination in the vicinity of Well 37344 and the "Boller Well". This zone represents an area more than a mile downgradient of the NBCS where substantial concentrations of organic contaminants have been detected.

Site E-76

Location: Proposed well site E-76 is located along East 104th Avenue, 1,450 ft east of Peoria Street.

Rationale: Proposed well site E-75 will be utilized to assess the extent of alluvial ground-water contamination in the vicinity of Well 37344 and the "Boller Well". This zone represents an area more than a mile downgradient of the NBCS where substantial concentrations of organic contaminants have been detected.

12.0 TASK 42

12.1 OBJECTIVES

The objectives of Task 42 are as follows:

- o Assess whether potential contamination exists in the soil or ground water of the North Plants area and to identify the analytes present;
- o To conduct a preliminary evaluation of the vertical and horizontal extent of contamination present in the North Plants; and
- o To provide site-specific information upon which to base the upcoming feasibility studies for eventual remediation.

These objectives are accomplished through chemical analyses of 213 Phase I and 166 Phase II soil samples, and ground water samples collected from the six alluvial wells installed during an extended Phase I survey.

The alluvial ground-water monitoring wells will be installed and sampled within the main manufacturing/demilitarization area to:

- o Provide an estimate of the vertical and areal extent of potential contamination within the alluvial aquifer;
- o Determine the alluvial aquifer thickness and direction of ground-water flow;
- o Delineate if Denver sand aquifers are in direct contact with saturated alluvium at each well site;
- o Estimate if potential ground-water contaminants may have originated from North Plants operations;
- o Provide information to the RI/FS database for designing remedial measures, if necessary; and
- o Provide information that will assist in performing remedial functions.

7/12/88

12.2 PROPOSED LOCATIONS

Site 25041

Location: Proposed well site 25041 is in the southeast quarter of Section 25, approximately 1,500 ft west of the east section line and 1,300 ft north of the south section line. One alluvial well is planned for this site.

Rationale: Proposed well site 25041 is located to provide upgradient water quality data.

Site 25042

Location: Proposed well site 25042 is in the southeast quarter of Section 25, approximately 2,050 ft west of the east section line and 1,750 ft north of the south section line. One alluvial well is planned for this site.

Rationale: Proposed well site 25042 is located in the Tank Farm 1403 area downgradient from Phase I soil Borings 36 and 45 where benzene was detected.

Site 25043

Location: Proposed well site 25043 is in the southeast quarter of Section 25, approximately 1,500 ft west of the east section line and 1,960 ft north of the south section line. One alluvial well is planned for this site.

Rationale: Proposed well site 25043 is located within a fuel oil spill site area downgradient of Task 42 Phase I soil boring 42 where benzene and DMMP were detected.

Site 25044

Location: Proposed well site 25044 is in the southeast quarter of Section 25 approximately 1,800 ft west of the east section line and 1,960 ft north of the south section line. One alluvial well is planned for this site.

7/12/88

Rationale: Proposed well site 25044 is located within a fuel oil spill site area downgradient of Task 42 Phase I soil Boring 40 and the chemical sump where DMMP was detected.

Site 25046

Location: Proposed well site 25046 is in the northeast quarter of Section 25 approximately 1,800 ft west of the east section line and 2,000 ft south of the north section line. One alluvial well is proposed at this site.

Rationale: Proposed well site 25046 is located downgradient of Building 1611 and Phase I soil Borings 27 and 50 where DMMP and chromium, respectively, were detected.

Site 25047

Location: Proposed well site 25047 is in the southeast quarter of Section 25 approximately 2,200 ft west of the east section line and 2,250 ft north of the south section line. One alluvial well is proposed at this site.

Rationale: Proposed well site 25047 is located downgradient of the main manufacturing and scrubber areas to determine if ground water may have been contaminated by operations in these areas.

13.0 TASK 44

13.1 OBJECTIVES

Task 44 is the long-term monitoring network designed to implement regional ground-water monitoring in both the onpost and offpost areas. The task will serve as the baseline or "trunk" program for all hydrologic investigations performed at RMA. Various other ground-water efforts are planned or are underway at RMA. These tasks deal with site specific investigations such as the boundary systems, primary potential sites, and/or potential migration pathways. Additionally, the various soil investigations contain certain ground-water components. These other ground-water activities are regarded as branch efforts which will augment the regional program with a more detailed level of understanding for the site-specific area in which the respective programs operate.

Functioning as the core hydrologic program, Task 44 is designed to satisfy the following objectives:

- o Assess the distribution and concentration levels of ground-water contaminants and monitor changes in water quality for both onpost and offpost areas;
- o Monitor and evaluate changes in water levels;
- o Evaluate and make recommended program modifications to this and other ground-water tasks; and
- o Identify areas of significant public health exposure.
- o Integrate all ground-water related efforts.

The satisfaction of these goals will provide personnel working with the RMA EA and FS groups with a characterization of contaminant hydrogeology and, as related to this document, provide a mechanism for identifying and filling data deficiencies between various hydrologic efforts conducted at RMA.

13.2 PROPOSED LOCATIONS

Site EP-53

Location: Proposed well site EP-53 is located 250 ft north of the south section line and 1,000 ft west of the east section line of Section 23, T2S, R67W.

Rationale: Proposed well sites EP-53 will provide hydrologic and water quality data downgradient of Basin F for both alluvial and Denver sand aquifers. Subsurface evaluations indicate that the proposed site will monitor ground-water flow and water quality in a major alluvial contaminant pathway originating from Basin F and consequently aid in a more detailed assessment of contaminant characterization and transport. Additionally, the Denver sand wells will provide chemical and stratigraphic information which will augment the Denver Fm investigation conducted under Task 36 by contributing upgradient water quality, geologic, and hydrologic data. Also, there are currently no well clusters in the area. Installation of the proposed well site will fill a gap in the areal distribution of regional cluster sites.

Site EP-54

Location: Proposed well site EP-54 is located 250 ft south of the north section line and 2,100 ft west of the east section line of Section 26, T2S, R67W.

Rationale: Proposed well site EP-54 will provide hydrologic and water quality data downgradient of Basin F in the alluvial aquifer. An evaluation of contaminant distribution and subsurface structures reveal that the site will monitor alluvial ground-water flow and water quality in a major contaminant pathway originating from Basin F and consequently aid in a more detailed assessment of contaminant characterization and transport. The proposed site will provide a monitoring point at a location where existing wells in the area are of undocumented construction.

Site EP-55

Location: Proposed well site EP-55 is located 50 ft south of the north section line and 2,450 ft west of the east section line of Section 26, T2S, R67E.

Rationale: Proposed well site EP-55 will provide hydrologic and water quality data downgradient of Basin F in the alluvial aquifer. An evaluation of contaminant distribution and subsurface structure reveal that the site will monitor alluvial ground-water flow and water quality in the area, and consequently aid in contaminant characterization and plume definition. Additionally, stratigraphic information obtained during drilling will augment the bedrock interpretation in the area. The proposed site will provide a monitoring point at a location where existing wells in the area are of undocumented construction.

Site EP-56

Location: Proposed well site EP-56 is located 100 ft south of the north section line and 2,000 ft east of the west section line of Section 26, T2S, R67W.

Rationale: Proposed well site EP-56 will provide hydrologic and water quality data downgradient of Basin F for both alluvial and Denver sand aquifers. Subsurface evaluations indicate that the proposed site will monitor ground-water flow and water quality in a possible alluvial contaminant pathway originating from Basin F and consequently aid in a more detailed assessment of contaminant characterization and plume definition. Additionally, the Denver sands wells will provide chemical and stratigraphic information which will augment the Denver Fm investigation conducted under Task 36 by contributing upgradient water quality, geologic, and hydrologic data. Also, there are currently no well clusters in the area. Installation of the proposed well site will fill a gap in the areal distribution of regional cluster sites.

Site EP-62

Location: Proposed well site EP-62 will be located in Section 34, T2S, R67W. Location will be finalized following an evaluation of new Shell well installation and sampling data.

Rationale: As a result of the data review it is believed that EP-62 should be installed in a cluster configuration to provide data which will aid in the evaluation of geology, hydrogeology, and contaminant distribution in the Denver Fm.

Site EP-64

Location: Proposed well site EP-64 is located 2,400 ft north of the south section line and 700 ft east of the west section line of Section 34, T2S, R67W.

Rationale: Proposed well site EP-64 will provide hydrologic and water quality data along a potential alluvial migration pathway originating from the rail classification yard or the lower lakes. An evaluation of the subsurface geology indicates that the site will monitor ground-water flow and water quality in an area of a possible confluence of two paleochannels and consequently provide the data to determine if this is the case. Additionally, the proposed well site fills a gap in the areal distribution of alluvial wells in the regional network and will aid in plume definition and water table interpretation.

Site EP-65

Location: Proposed well site EP-65 is located 2,200 ft north of the south section line and 550 ft west of the east section line of Section 34, T2S, R67W.

Rationale: Proposed well site EP-65 will provide hydrologic and water quality data for both alluvial and Denver sands aquifers. Subsurface evaluations indicate that the proposed site will monitor ground-water flow and water quality in a paleochannel originating from the South Plants and consequently augment plume definition and flow direction. Additionally, the site will provide geologic information which will refine current bedrock and

07/13/88

Denver sands interpretation. Installation of the site will fill a gap in the areal distribution of regional cluster sites and provide a distal monitoring point for Denver sands monitoring.

Site EP-66

Location: Proposed well site EP-66 is located 1,100 ft south of the north section line and 1,250 ft west of the east section line of Section 3, T2S, R67W.

Rationale: Proposed well site EP-66 will provide hydrologic and water quality data for the alluvial and Denver sand aquifers in an area of sparse information west of the South Plants. Subsurface evaluations indicate the presence of a paleochannel in the area of the lower lakes with which contamination seems to coincide. Installation of this well site will better define contaminant extent and character, as well as add to the interpretation of Denver sands geology.

Site EP-67

Location: Proposed well site EP-67 will be located in Section 35, T2S, R66W. Location will be finalized following evaluation of new Shell and EBASCO well installations.

Rationale: Evaluated of Shell and EBASCO activities in the area of the proposed site resulted in the decision to install a cluster combination to augment other cluster configurations in the area and thereby provide additional geologic and hydrogeologic data regarding the Denver Fm.

Site EP-71

Location: Proposed well site EP-71 is located 1,400 ft south of the north section line and 1,050 ft west of the east section line of Section 22, T2S, R67W.

Rationale: Proposed well site EP-71 will provide geologic, hydrologic, and water quality data for both alluvial and Denver sands aquifers. The proposed site fills a gap in the areal distribution of monitoring well locations.

Site EP-72

Location: Proposed well site EP-72 is located 1,300 ft south of the north section line and 1,800 ft east of the west section line of Section 23, T2S, R67W.

Rationale: Proposed well site EP-72 will provide geologic, hydrologic, and water quality data for both alluvial and Denver sands aquifers. The proposed site fills a gap in the areal distribution of monitoring well locations.

Site EP-74

Location: Proposed well site EP-74 is located 1,600 ft north of the south section line and 1,400 ft west of the east section line of Section 24, T2S, R67W.

Rationale: Proposed well site EP-74 will provide geologic, hydrologic, and water quality data for alluvial and Denver sands aquifers. The proposed location will monitor alluvial ground-water flow and water quality along the major contamination plume upgradient of the NBCS and will refine plume definition and contaminant characterization. Additionally, the Denver sand wells will provide chemical and stratigraphic information which will augment the Denver Fm investigation conducted under Task 36 by contributing upgradient water quality, hydrologic, and geologic data. The installation further provides an additional regional cluster site for alluvial and Denver water quality and hydrologic monitoring.

Site EP-75

Location: Proposed well site EP-75 is located 2,600 ft south of the north section line and 350 ft west of the east section line of Section 23, T2S R67W.

Rationale: Proposed well site EP-75 will provide geologic, hydrologic, and water quality data for alluvial and Denver sands aquifers. The proposed location will monitor alluvial ground-water flow and water quality along the major contamination plume upgradient of the NBCS and will refine plume definition and contaminant characterization. Additionally, the Denver sands wells will provide chemical and stratigraphic information which will augment

the Denver Fm investigation conducted under Task 36 by contributing upgradient water quality, hydrologic, and geologic data. The installation further provides an additional regional cluster site for alluvial and Denver water quality and hydrologic monitoring.

APPENDIX A--ONPOST WELL PRIORITY RATIONALE

ONPOST WELL PRIORITY RATIONALE

ESE

Site EP-01

Proposed well site EP-01 will replace existing alluvial Well 22008 which does not fully penetrate the entire thickness of the saturated alluvium. This well has been given a secondary priority because the existing well can be used. However, a fully penetrating well would provide data for the entire zone of interest.

Site EP-01A

Proposed well site EP-01A is a secondary priority alluvial site because there are existing wells in this area that can be used for monitoring contaminant flow paths and plume definition in the southern portion of the NWBCS. However, these wells are largely of undocumented construction.

Site EP-02

Proposed well site EP-02 is a primary priority alluvial well because a good quality well which monitors the entire saturated thickness is needed to ensure that contamination does not migrate around the NWBCS. Existing wells in the area are largely of undocumented construction and do not monitor the entire thickness of saturated alluvium.

Site EP-03

Proposed well site EP-03 is a primary priority alluvial well because a good quality well which monitors the entire saturated thickness is needed to ensure that contamination does not migrate around the NWBCS. Existing wells in the area are largely of undocumented construction and do not monitor the entire thickness of saturated alluvium.

Site EP-04

Proposed well site EP-04 is a primary priority site because a fully penetrating alluvial well is needed here to better define contaminant transport in the center portion of the plume treated by the NWBCS. Existing

07/12/88

Well 23160, which site EP-04 will replace, does not fully screen the entire thickness of saturated alluvium.

Site EP-05

Proposed well site EP-05 will replace existing alluvial Well 23013 which does not screen the entire saturated alluvium. This site is a secondary priority because primary priority has been given to installing new wells at sites deemed more critical as adequate monitoring of the contaminant plumes should be achieved with the installation of primary priority wells.

However, if after evaluating the data from primary priority sites and existing wells, it is felt that an additional site is needed to better delineate the lateral extent of the plume being treated by the NBCS, then an alluvial well at site EP-05 may be installed.

Site EP-06

Proposed well site EP-06 will replace existing Well 23106 which does not screen the entire thickness of saturated alluvium. This site is a secondary priority because primary priority has been given to installing new wells at sites deemed more critical as adequate monitoring of the contaminant plumes should be achieved with the installation of primary priority wells.

However, if after evaluating the water quality and hydrologic data from primary priority sites and existing wells, it is determined that an additional alluvial well is needed to better characterize the alluvial plume being treated by the NBCS, then an alluvial well may be installed at site EP-06.

Site EP-07

Proposed well site EP-07 will replace existing alluvial Well 24162 which does not screen the entire saturated alluvium. This site is a tertiary priority because installation will depend on evaluating the water quality and hydrologic data from the primary priority sites, as well as existing sites, and assessing whether an additional site is required to characterize the alluvial plume being treated by the NBCS.

Site EP-08

Proposed well site EP-08 will replace existing alluvial Well 24180 which does not fully screen the saturated alluvium. This site is a secondary priority because primary priority has been given to installing new wells at sites deemed more critical to monitor the concentration and lateral extent of the contaminant plume further upgradient of the NBCS. However, if after evaluating the water quality and hydrologic data from the primary priority sites and existing wells, it is determined that a better completed alluvial well is needed to monitor contaminant concentrations immediately upgradient of the soil-bentonite barrier, then an alluvial well may be installed at site EP-08.

Site EP-09

Proposed well site EP-09 will replace existing alluvial Well 24181 which does not screen the entire saturated alluvium. This site is a tertiary priority because primary priority has been given to installing new wells at sites deemed more critical to monitor the concentration and lateral extent of the contaminant plume further upgradient of the NBCS. However, if after evaluating the water quality and hydrologic data from the primary priority sites and existing wells, it is determined that a better completed alluvial well is needed to monitor contaminant concentrations immediately upgradient of the soil-bentonite barrier, then an alluvial well may be installed at site EP-09.

Site EP-10

Proposed well site EP-10 will replace existing alluvial Well 24182 which does not screen the entire saturated alluvium. This site is a tertiary priority because primary priority has been given to installing new wells at sites deemed more critical to monitor the concentration and lateral extent of the contaminant plume further upgradient of the NBCS. However, if after evaluating the water quality and hydrologic data from the primary priority sites and existing wells, it is determined that a better completed alluvial well is needed to monitor contaminant concentrations immediately upgradient of the soil-bentonite barrier, then an alluvial well may be installed at site EP-10.

Site EP-11

Proposed well site EP-11 will replace existing Well 24115 which does not screen the entire thickness of saturated alluvium. This site is a primary priority because it is essential for the definition of the plume which is treated by the NBCS.

Site EP-12

Proposed well site EP-12 will replace existing Well 24106 which does not screen the entire thickness of saturated alluvium. This site is a tertiary priority because it is not located within the historical plume being treated by the NBCS.

Site EP-13

Proposed well site EP-13 will replace existing Well 24113 which does not screen the entire thickness of saturated alluvium. This site is a primary priority because it is essential for the definition of the plume which is treated by the NBCS. Historically, Well 24113 has given inconsistent water quality data.

Site EP-14

Proposed well site EP-14 will replace existing Well 24008 which does not screen the entire thickness of saturated alluvium. This site is a primary priority because it is essential for the definition of the plume which is treated by the NBCS. Historically, Well 24008 has given inconsistent water quality data.

Site EP-16

Proposed well site EP-16 will replace existing Well 24010 which does not screen the entire thickness of saturated alluvium. This site was a primary priority because it was needed to provide reliable hydrologic and water quality data to further define and characterize the contaminant plume between the North Plants and Basin F and the NBCS. This site has been down graded to secondary priority as a result of the installation at Site EP-74 of an alluvial, first Denver, second Denver cluster. The alluvial well at EP-74 should provide the necessary data to satisfy the EP-16 requirements.

Site EP-17

Proposed well site EP-17 is a secondary priority new alluvial well site. This site has been assigned a secondary priority because primary priority has been given to sites which are critical to monitor the historical plume being treated by the NBCS.

Site EP-18

Proposed well site EP-18 is a tertiary priority new alluvial well site. This site has been assigned a tertiary priority because higher priority has been given to sites which are critical to monitor the historical plume being treated by the NBCS. Installation will be dependant upon evaluation of water quality, hydrologic, and geologic data obtained from the alluvial well at site EP-74.

Site EP-19

The pilot corehole and first sandstone well at this site are primary priority. The pilot corehole is a primary priority because it is needed to further define the bedrock geology in this area. The first sandstone well is required to assess water quality and water levels downgradient from wells located in the same sandstone unit that are closer to the soil-bentonite barrier. Installation of a second sandstone well is a secondary priority that may need to be undertaken after evaluating the data from the first sandstone primary priority site. The first Denver installation has been downgraded to secondary priority based on the lithologic data obtained from the corehole.

Site EP-20

The pilot corehole at this site is a primary priority because it is needed to collect geologic information on the configuration of sandstone units. The installation of a first sandstone well is a secondary priority. The first sandstone wells at sites EP-21 and EP-19 are considered higher priority and will be installed first. As a result of EP-21, EP-19, and the corehole at EP-20, the data obtained indicated the need for first Denver and second Denver wells. These were assigned primary priority.

Site EP-21

Proposed well site EP-21 is for drilling a primary priority corehole and installing a primary priority first sandstone well. The corehole is needed to aid in the assessment of the configuration of the Denver sands at this location. The first sandstone well is a primary priority because it is needed to assess water quality and water levels downgradient from wells located in the same sandstone unit that are closer to the soil-bentonite barrier. Installation of a second sandstone well is a secondary priority that may need to be undertaken after evaluating the data from the first sandstone primary priority site.

Site EP-22

This site is for drilling a secondary priority pilot corehole and installation of a secondary priority first sandstone well. These activities will depend upon water quality and water level data obtained from previously installed wells at sites E-33 and E-34, which are first sandstone wells installed just to the east and west of the proposed site, respectively.

Site EP-23

Proposed well site EP-23 is for the installation of a primary priority alluvial well. This site is a primary priority because the wells within 500 ft of this site are of undocumented construction. In addition, the well is needed to provide hydrologic data to determine plume flow directions as well as water quality information for contaminant characterization upgradient of the NBCS.

Site EP-25

This site is for a secondary priority pilot corehole and first sandstone well upgradient of the NBCS. This site is a secondary priority because the activities can be more effectively undertaken after evaluating the data from drilling and well installation associated with the primary priority site EP-27. Results obtained from the EP-27 installation resulted in the assignment of primary priority to the corehole at the site.

Site EP-26

Proposed well site EP-26 is for a secondary priority pilot corehole and first sandstone well upgradient of the NBCS. This site is a secondary priority because the activities can be more effectively undertaken after evaluating the data from drilling and well installation associated with the primary priority site EP-27. The installation at EP-27 provided data which indicated that all efforts at this site be assigned primary priority.

Site EP-27

This upgradient site is for a primary priority pilot corehole and first Denver sandstone well. This drilling and installation is a primary priority because it will assist in defining geology, water quality, and hydrologic conditions in a major first sandstone unit. This well will also assist in determining points of entry for contamination into this unit. Results from drilling and sampling in the area indicated that a second Denver well was of primary priority at the site.

Site EP-28

This site is for drilling a primary priority corehole and installation of a secondary priority first Denver sandstone well. The corehole will be used to define the extent of the first sandstone in this downgradient area. The first sandstone well is a secondary priority because the need to install it will be evaluated based upon data obtained from the primary priority wells at sites EP-19 and EP-21. Results from EP-19 and EP-21 indicated that the first Denver installation be assigned primary priority.

Site EP-29

Proposed well site EP-29 has been designated as a secondary priority location. The site will be used, if necessary, to supplement the EBASCO study of the North Plants. The site will be reevaluated following a review of the Task 42 Technical Plan. Following review of the Task 42 Technical Plan, Site EP-29 was assigned primary priority.

Site EP-30

Proposed well site EP-30 has been designated as a secondary priority location. The site will be used, if necessary, to supplement the EBASCO

study of the North Plants. The site will be reevaluated following a review of the Task 42 Technical Plan.

Site EP-31

Proposed well site EP-31 has been designated as a tertiary priority location because the location supplements the proposed regional surface water study rather than satisfying a primary Task 21 objective. Additionally, it is felt that with the installation of wells at sites EP-32, EP-33, and EP-34 and the presence of existing Wells 25011, 25012, 25013, and 25014, the site may not be necessary and consequently waived. The site will be reevaluated following completion of activities at sites EP-32, EP-33, and EP-34.

Site EP-32

Proposed well site EP-32 has been designated as a secondary priority location because the site supplements the proposed regional surface water program rather than satisfying a primary Task 21 objective. The site will be reevaluated following the determination of the scope of the surface water program under Task 44.

Site EP-33

Proposed well site EP-33 has been designated as a secondary priority location because the site supplements the proposed regional surface water program rather than satisfying a primary Task 21 objective. The site will be reevaluated following the determination of the scope of the surface water program under Task 44.

Site EP-34

Proposed well site EP-34 has been designated as a secondary priority location because the site supplements the proposed regional surface water program rather than satisfying a primary Task 21 objective. The site will be reevaluated following the determination of the scope of the surface water program under Task 44.

Site EP-35

Proposed well site EP-35 has been designated as a primary priority location. The site will contribute the achievement of Task 1 primary objectives by providing upgradient ground-water monitoring in the vicinity of Basin A.

Site EP-36

Proposed well site EP-36 has been designated as a secondary priority location. The site is located in proximity to existing Wells 36075, 01008, and 01051 and possible installations under Task 26 and Task 2. These wells may be used to satisfy primary task objectives. The site will be reevaluated following a review of installations proposed and/or completed under Task 26 and Task 2.

Site EP-37

Proposed well site EP-37 has been designated as a secondary priority location. The site is located in proximity to existing Wells 36067 and 36104. These wells may be used to satisfy primary task objectives. The site will be reevaluated following a determination of source specific monitoring methodologies.

Site EP-38

Proposed well site EP-38 has been designated as a primary priority location. Installation of the well will contribute to the achievement of Task 1 primary objectives by providing downgradient monitoring in the area of Site 36-17.

Site EP-39

Proposed well site EP-39 has been designated as a secondary priority location. The site is located in proximity to recently determined existing Wells 36154 and 36155. These wells may be utilized to satisfy primary task objectives. The site will be reevaluated following a review of these wells and a determination of source specific monitoring methodologies.

Site EP-41

Proposed well site EP-41 has been designated as a primary priority location. Installation of the proposed wells will contribute to the achievement of

Task 1 primary objectives by providing a monitoring cluster in the Basin A outflow area.

Site EP-42

Proposed well site EP-42 has been designated as a tertiary priority location. The site will be used, if necessary, to supplement Task 26 activities. The site will be reevaluated following a review of Task 26 activities.

Site EP-43

Proposed well site EP-43 has been designated as a primary priority location for the completion of a corehole and a secondary priority location for the installation of a first water monitoring well. A determination of structure and stratigraphy at the site must be made prior to a decision on the well installation as the proposed location lies in an area of complex geology.

Site EP-44

Proposed well site EP-44 has been designated as a primary priority location. The site will contribute to the achievement of Task 19 primary objectives by providing a monitoring cluster to assess ground-water quality and flow between Basin B and Basin C and Basin D.

Site EP-45

Proposed well site EP-45 has been designated as a tertiary priority location. The site is located in proximity to recently determined existing Wells 26005, 26068, and 26069. These wells may be used to satisfy primary task objectives. The site will be reevaluated following a determination of source specific monitoring methodologies.

Site EP-46

Proposed well site EP-46 has been designated as a tertiary priority location. The site will be reevaluated following a determination of source specific monitoring methodologies.

Site EP-47

Proposed well site EP-47 has been designated as a primary priority location. The site will contribute to the achievement of Task 19 primary objectives by providing first water monitoring in the ground-water flow path out of Basin E.

Site EP-48

Proposed well site EP-48 has been designated as a secondary priority location. The site is located in proximity to existing Wells 26024, 26049, and 26025. These wells may be used to satisfy primary task objectives. The site will be reevaluated following a determination of source specific monitoring methodologies.

Site EP-49

Proposed well site EP-49 has been designated as a primary priority location for the completion of a corehole. Any future wells installations will be determined following evaluation of the acquired geologic and hydrologic data since the proposed location lies in an area of complex geology. The resolution of this site will contribute to the achievement of Task 19 primary objectives. Following evaluation of data obtained from other installations in the area, alluvial and first Denver installations were assigned primary priority.

Site EP-50

Proposed well site EP-50 has been designated as a secondary priority location. Existing Wells 26145, 26146, and 26147 lie in proximity to the proposed site and may be used to satisfy Task 19 primary objectives. The site will be reevaluated following a review of the existing wells.

Site EP-52

Proposed well site EP-52 has been designated a primary priority location. The site will contribute to the achievement of Task 19 primary objectives by providing a monitoring cluster in an area previously devoid of ground-water wells. Following evaluation of data obtained from the corehole, the second Denver installation was assigned secondary priority.

Site EP-53

Proposed well site EP-53 is a primary priority site for the installation of a pilot Denver corehole, an alluvial well, and two Denver wells. The installation of this cluster site is a primary priority because there are currently no cluster sites in the area, and this site will fill a significant data gap in the areal distribution of regional cluster sites. The alluvial well will monitor ground-water flow and water quality in a major alluvial contaminant pathway originating from Basin F. The Denver sand wells will provide water quality and hydrologic information which will aid in the Denver Fm investigation conducted under Task 36. The pilot corehole is a primary priority because it will provide important geologic data in the assessment of the configuration of potential water bearing units in the Denver emanating from Basin F.

Site EP-54

Proposed well site EP-54 is for the installation of a primary priority alluvial well. This site is a primary priority because it will provide a monitoring point downgradient of Basin F where existing wells are of undocumented construction. This site is also essential to the Basin F interim response action.

Site EP-55

Proposed well site EP-55 is for the installation of a primary priority alluvial well. This site is a primary priority because it will provide a monitoring point downgradient of Basin F where existing wells are of undocumented construction. This site is also essential to the Basin F interim response action.

Site EP-56

Proposed well site EP-56 is a primary priority site for the installation of a pilot Denver corehole, an alluvial well, and a Denver well. The installation of a second Denver sand well is to be determined based on an evaluation of the historical water quality of this unit. The installation of this cluster site is a primary priority because there are currently no cluster sites in the area, and this site will fill a significant data gap in the areal distribution of regional cluster sites. The alluvial well will

07/13/88

monitor ground-water flow and water quality in a major alluvial contaminant pathway originating from Basin F. The first Denver sand well will provide water quality and hydrologic information which will aid in the Denver Formation investigation conducted under Task 36. The pilot corehole is a primary priority because it will provide important geologic data in the assessment of the configuration of potential water bearing units in the Denver emanating from Basin F. Results obtained from the corehole indicated that the second installation was a primary priority.

Site EP-59

Proposed well site EP-59 has been designated a secondary priority location. Numerous existing wells in proximity to the proposed site may be used to satisfy Task 19 primary objectives. The site will be reevaluated following a determination of source specific monitoring methodologies.

Site EP-62

Following a review of existing Army and Shell wells in the area the alluvial, corehole, and first Denver efforts were assigned primary priority, as additional geologic, hydrogeologic, and chemical data were required for an evaluation of the Denver Fm in the area.

Site EP-64

Proposed well site EP-64 is for the installation of a primary priority alluvial well. This site is a primary priority because it will fill a significant data gap in the regional alluvial monitoring network. This site is also needed to aid in the assessment of whether this location is in an area of possible confluence of two paleochannels. The site appears to be in an area of dry alluvium. As a result its priority has been downgraded to secondary.

Site EP-65

Proposed site EP-65 is a primary priority site for the installation of one alluvial well, two Denver wells, and the drilling of a pilot Denver corehole. This alluvial site is necessary to assess the alluvial water quality and direction of flow in a paleochannel originating from the South Plants. The Denver sand wells are needed to assess the possibility of

Denver contamination in this area of Section 34. The pilot Denver corehole is a primary priority because it will provide geologic information which will refine current bedrock interpretation and potential water bearing units in the Denver. Installation of the site will fill a significant data gap in this area.

Site EP-66

As a result of a review of existing wells in the area and the completion of the corehole the alluvial and first Denver installations have been assigned primary priority.

Site EP-67

As a result of a review of existing wells, the installation of Shell wells, and the completion of the corehole, the alluvial, first Denver, and second Denver installations have all been assigned primary priority to provide the necessary geologic, hydrogeologic, and chemical data to evaluate the Denver Fm.

Site EP-71

Proposed Site EP-71 is a secondary priority site for the installation of one alluvial well, two Denver wells, and the drilling of a pilot Denver corehole. This site is a secondary priority because primary priority has been given to those sites that are more critical for monitoring historical contaminant migration. Based upon OAS input and a review of hydrogeologic and geologic data, installations at EP-71 have been upgraded to primary priority.

Site EP-72

Proposed well site EP-72 is a primary priority site for the drilling of a pilot corehole and installation of one alluvial well and two Denver sand wells. The installation of this cluster site is a primary priority because there are currently no cluster sites in the area and this site will fill a significant data gap in the areal distribution of regional cluster sites. An alluvial well will be installed, if there is alluvial water at this site, to monitor flow that may be going around the NBCS. The Denver sand wells and pilot Denver corehole are a primary priority because they will provide

water quality, hydrologic, and geologic data which will aid in the assessment of the configuration of Denver aquifers near the NBCS that is being conducted under Task 36.

Site EP-74

Proposed well site EP-74 is a primary priority site for the drilling of a pilot corehole and installation of one alluvial well and two Denver sand wells. The installation of this cluster site is a primary priority because there are currently no cluster sites in the area and this site will fill a significant data gap in the areal distribution of regional cluster sites. The alluvial well is needed at this location to provide hydrologic data to determine plume flow direction, as well as water quality information for contaminant characterization upgradient of the NBCS. The Denver sand wells and pilot Denver corehole are a primary priority because they will provide water quality, hydrologic, and geologic data which will aid in the assessment of the configuration of Denver aquifers near the NBCS that is being conducted under Task 36.

Site EP-75

Proposed well site EP-75 is a primary priority site for the drilling of a pilot corehole and installation of one alluvial well and two Denver sand wells. The installation of this cluster site is a primary priority because there are currently no cluster sites in the area and this site will fill a significant data gap in the areal distribution of regional cluster sites. An alluvial well will be installed if there is alluvial water at this site, to monitor flow that may be going around the NBCS. The Denver sand wells and pilot Denver corehole are a primary priority because they will provide water quality, hydrologic, and geologic data which will aid in the assessment of the configuration of Denver aquifers near the NBCS that is being conducted under Task 36.

Site EP-76

This pilot corehole at this site was drilled to provide geologic data for cross sections to correlate sandstone units that are beneath the pilot barrier. It was anticipated that all the sandstone units that are present at the barrier would be present at this location and a cluster site could be

07/14/88

installed. However, this was not the case and no wells were installed. This corehole will also provide geologic data for any future interpretive work in the Denver Fm and/or any future well installations at this site.

EBASCO

Due to the site specific and/or problem specific nature of the EBASCO tasks, all sites were assigned primary priority as installation of these wells contributed directly to the achievement of the respective tasks objectives.

APPENDIX B--OFFPOST WELL PRIORITY RATIONALE

OFFPOST WELL PRIORITY RATIONALE

Site E-32

Proposed well site E-32 is a primary priority site which is needed to assess the water quality and water flow directions of the first and second Denver sand units downgradient of the NBCS. This is a primary priority site because it is located directly downgradient of Denver dewatering Well 23342 which is suspected of being poorly completed and may provide a mechanism for cross contamination between aquifers. The pilot corehole is a primary priority because it is needed to define the extent and configuration of bedrock sand units downgradient of the NBCS.

Site E-33

At proposed well site E-33, the pilot corehole and first Denver sandstone well are a primary priority. The well is a primary priority because there are currently no functional first sand Denver wells in this area. This well will be used to fill this hydrologic and water quality data gap. A second Denver sand well at this site is considered a tertiary priority because historically this unit has not shown significant levels of contamination relative to other units that have been identified at the NBCS. The pilot Denver corehole is a primary priority because it is needed to assess the extent and configuration of potential water bearing units in the Denver downgradient of the NBCS.

Site E-34

At proposed well site E-34, the pilot corehole and first Denver sand well are primary priority activities. The first Denver sand well is a primary priority because there are no water quality Denver wells in service in this area. Water quality data is needed here to assess if this Denver unit is acting as a contaminant pathway beneath the NBCS. The second Denver sand well is considered a tertiary priority because historically this unit has not shown significant levels of contamination relative to other units that have been identified at the NBCS. The pilot Denver corehole is a primary priority because it will provide important geologic data in the assessment of the lateral and northerly extent of potential water bearing units in the

Denver. There are presently no Denver wells or borings in service in this area downgradient of the NBCS.

Site E-36

Proposed well site E-36 is a tertiary priority site for a possible cluster of one alluvial and two Denver wells. This site would be utilized to assess the water quality and water flow directions in the alluvium and the first and second Denver sand units identified at the site. The alluvial well is considered tertiary priority because it is a considerable distance to the east of the major alluvial contaminant plumes near the NBCS. The Denver wells are considered tertiary priority because Denver units in this area have not shown significant contamination historically.

Site E-38

Proposed well site E-38 is a primary priority site for the installation of one alluvial well, two Denver wells, and the drilling of a pilot Denver corehole. This site is necessary to assess the extent of alluvial contamination along the inferred First Creek paleochannel and the possibility of Denver contamination to the northwest of the NBCS. These installations are primary priority because they will fill a significant data gap in this area.

Site E-39

Proposed well site E-39 is a primary priority site for the installation of one alluvial well, two Denver wells, and the drilling of a pilot Denver corehole. This site is primary priority because there are currently no alluvial or Denver wells in this area and these wells are needed to assess the water quality of the alluvium and the Denver sands downgradient of the NBCS. The pilot corehole is a primary priority because it will provide important geologic data in the assessment of the lateral and northerly extent of potential water bearing units in the Denver.

Site E-40

Proposed well site E-40 is a primary priority for drilling a pilot corehole and installing one alluvial well and two Denver wells. The alluvial well will replace Well 37305 which has no construction documentation. A good

quality alluvial well is necessary at this location to help define the concentration and extent of contaminants along the First Creek paleochannel. The Denver wells are primary priority because they are needed to assess the downgradient water quality and water flow directions in Denver sand units which have been identified at the NBCS. There are presently no Denver wells in this area.

Site E-41

Proposed well site E-41 is for drilling a tertiary priority corehole and installing a secondary priority alluvial well and two tertiary priority Denver wells. The alluvial well is a secondary priority because it may be needed to assess the extent and concentration of contaminants along the First Creek paleochannel. The Denver wells and pilot corehole are a tertiary priority. The installation of these wells will be dependant upon whether specific data gaps are identified in the Denver at this location. Data gaps at this location will be most effectively identified by evaluating water quality, geologic, and hydrologic data from sites E-32 and E-40.

Site E-42

Proposed well site E-42 is a primary priority for an alluvial well because it will provide important data on the extent and concentration of contaminants to the north of First Creek. The pilot corehole and Denver wells are a tertiary priority and installation will depend on whether specific data gaps are identified by evaluating geologic, hydrologic, and water quality data from sites E-32 and E-40.

Site E-43

Proposed Site E-43 is a secondary priority site for the drilling of a pilot Denver corehole and the installation of an alluvial well. The installation of an alluvial well at this site is dependant upon water quality and hydrologic data from sites E-63, E-47, and E-74. A pilot boring at this location may be necessary to define the geology north of the eastern portion of the NBCS. The decision to drill this corehole will be made after evaluating geologic, hydrologic, and water quality data from site E-34.

Site E-44

Proposed well site E-44 is a primary priority alluvial site to assess the concentration and extent of contaminants along the First Creek paleochannel. The Denver wells are tertiary priority because their installation will depend on assessing water quality, hydrologic, and geologic data from sites E-39 and E-40.

Site E-45

Proposed well site E-45 is a secondary priority site for the drilling of a pilot corehole and the installation of two Denver wells at the site of existing alluvial Well 37323. It is a secondary priority site because the installation of these wells will depend on water quality, hydrologic, and geologic data from Denver wells at sites E-63, E-32, and E-33. A tertiary alluvial well has also been proposed for this site to replace Well 37323 which has no construction documentation. Site E-64 may be used in lieu of this site.

Site E-46

Proposed well site E-46 is a primary priority alluvial site. This site is needed to define a suspected bedrock paleochannel and determine the concentration and extent of contaminants in this area of Section 13. The pilot Denver corehole is a primary priority to define the extent and configuration of Denver sands downgradient of the NBCS. There are currently no Denver borings or wells in this area of Section 13. The Denver wells are tertiary priority and installation is dependent upon water quality, hydrologic, and geologic data obtained at sites E-63, E-33, and E-34.

Site E-47

Proposed well site E-47 is a primary priority alluvial site. This site is needed to define a suspected bedrock paleochannel and determine the concentration and extent of contaminants in this area of Section 13. The pilot Denver corehole is a primary priority to define the extent and configuration of Denver sands downgradient of the NBCS. There are currently no Denver borings or wells in this area of Section 13. The Denver wells are tertiary priority and installation is dependent upon water quality, hydrologic, and geologic data obtained at sites E-63, E-33, and E-34.

Site E-48

Proposed site E-48 is a secondary priority alluvial well that may be required to assess the lateral extent and depth of the alluvial channel, and the extent and concentration of contaminants. Installation of this well will be dependent upon evaluating data from the alluvial well at E-47.

Site E-49

Proposed well site E-49 is for installation of two Denver wells at the site of existing alluvial Well 37327. The Denver wells at this site are tertiary priority because Denver units at this location do not appear to be downgradient of significant Denver contamination associated with RMA.

Site E-50

Proposed well site E-50 is for the installation of a primary priority alluvial well. This well is needed to assess the concentration and extent of contaminants along the First Creek paleochannel. Denver wells at this site are tertiary priority because they will depend upon water quality, hydrologic, and geologic data obtained from upgradient sites.

Site E-51

Proposed well site E-51 is for the drilling of a tertiary priority pilot corehole and the installation of two tertiary priority Denver wells. Drilling of the pilot corehole and installation of the Denver wells will be dependent upon water quality, hydrologic, and geologic data obtained from upgradient sites.

Site E-52

Proposed well site E-52 will be used for the installation of one alluvial well. This well is a primary priority and is needed to define the extent of contamination in the southeast corner of Section 11 near the Boller well.

Site E-53

Proposed well site E-53 is for the drilling of a pilot corehole and the installation of one primary priority alluvial well and two tertiary priority Denver wells. The alluvial well will be used to assess the water quality, and alluvial hydrogeology upgradient of the Boller well. The Denver wells

and pilot corehole are tertiary priority and installation is dependent upon the evaluation of data collected from primary priority upgradient Denver wells.

Site E-54

Proposed well site E-54 is for the drilling of a pilot corehole and the installation of one alluvial well and two Denver wells. All activities at this site are tertiary priority. Installation of the alluvial well will depend upon the water quality and hydrogeologic data obtained from site E-76. Drilling the pilot corehole and installation of the Denver wells is dependent upon water quality and hydrogeologic data obtained from upgradient Denver wells.

Site E-55

Proposed well site E-55 is a primary priority alluvial site that will fill a data gap downgradient of the NWBCS. It will be used to assess the water quality in the offpost area between the NWBCS and production wells being proposed by SACWSD.

Site E-57

Proposed well site E-57 is for the installation of one alluvial well. This is a tertiary priority alluvial well site. Installation at this site will be dependent upon an assessment of water quality and hydrologic data at alluvial well sites E-75, E-58, E-53, E-64, and E-76.

Site E-58

Proposed well site E-58 is a primary priority alluvial site because it is needed to assess the concentration and extent of contaminants downgradient of the Boller well. Hydrologic data from this well will be used to delineate alluvial ground-water flow directions.

Site E-59

Proposed well site E-59 is for the installation of one alluvial well. This is a primary priority well. This site is necessary to define the extent and concentration of contaminants near the Boller well.

Site E-60

Site E-60 is for the installation of a tertiary priority alluvial well. This site would be utilized to help define the extent and concentration of alluvial ground-water contaminants in the area downgradient of O'Brian Canal and Burlington Ditch. This area has historically shown lower levels of contamination in comparison to the area between O'Brian Canal and the RMA north boundary. Installation of a well at this site will be dependent upon evaluation of water quality and hydrogeologic data from upgradient primary priority wells.

Site E-61

Site E-61 is for the installation of a tertiary priority alluvial well. This site would be utilized to help define the extent and concentration of alluvial ground-water contaminants in the area downgradient of O'Brian Canal and Burlington Ditch. This area has historically shown lower levels of contamination in comparison to the area between O'Brian Canal and the RMA north boundary. Installation of a well at this site will be dependent upon evaluation of water quality and hydrogeologic data from upgradient primary priority wells.

Site E-62

Site E-62 is for the installation of a secondary priority alluvial well. This site would be utilized to help define the extent and concentration of alluvial ground-water contaminants in the area downgradient of O'Brian Canal and Burlington Ditch. This area has historically shown lower levels of contamination in comparison to the area between O'Brian Canal and the RMA north boundary. Installation of a well at this site will be dependent upon evaluation of water quality and hydrogeologic data from upgradient primary priority wells.

Site E-63

Proposed site E-63 is a primary priority site for the drilling of a pilot corehole and the installation of a first Denver sand well and an alluvial well. These activities are needed to assess alluvial and Denver water quality and hydrogeology in an area downgradient of the NBCS where there is presently no monitoring or geologic information. The installation of a

second sand well at this site is considered a secondary priority because corresponding units at the NBCS have not historically shown significant contamination.

Site E-64

The alluvial well at site E-64 is a primary priority. This site is needed to assess whether a well-defined alluvial channel exists in this area and if such a channel may be acting as a primary pathway for contaminant migration to areas further north. The drilling of a pilot corehole and installation of Denver wells are tertiary priority and installation is dependent upon water quality and hydrogeologic data obtained from Denver wells upgradient.

Site E-65

The alluvial well at site E-65 is a primary priority. This well is needed to assess the extent and concentration of contaminants along the First Creek paleochannel. The drilling of a pilot corehole and installation of a first Denver sand well at this site is a secondary priority. The installation of a second Denver sand well is a tertiary priority. Denver drilling and well installation will depend upon water quality and hydrogeologic data obtained from sites E-39 and E-40.

Site E-66

Proposed well site E-66 is a primary priority and will replace Well 37332 which does not screen the entire saturated alluvium. A fully penetrating well offpost and downgradient of the NWBCS will provide more reliable water quality and hydrogeologic data to monitor the performance and operation of the system.

Site E-67

Proposed well site E-67 will replace existing Well 37334. This site is a primary priority because the existing well does not screen the entire saturated alluvium and there has recently been contamination detected in this area downgradient of the NWBCS. A fully penetrating well will provide more reliable hydrogeologic and water quality data to monitor the performance and operation of the system.

07/13/88

Site E-68

Proposed well site E-68 will replace existing Well 37330. The existing well does not screen the entire saturated alluvium. This site is a secondary priority because installation is dependent upon the evaluation of hydrogeologic data obtained from site E-67.

Site E-69

Proposed well site E-69 is a primary priority borehole site. This site is needed to define alluvial and Denver geology just downgradient of the NBCS. There is presently no geologic information in this area.

Site E-70

Proposed well site E-70 will replace Well 37308 which has no construction documentation. This well has been assigned a secondary priority. Primary priority has been given to those wells which are needed to fill data gaps where there are presently no wells.

Site E-71

Proposed well site E-71 will replace Well 37309 which has no construction documentation. This well has been assigned a secondary priority. Primary priority has been given to those wells which are needed to fill data gaps where there are presently no wells.

Site E-72

Proposed well site E-72 will replace Well 37313 which has no construction documentation. This well has been assigned a secondary priority. Primary priority has been given to those wells which are needed to fill data gaps where there are presently no wells.

Site E-73

Proposed well site E-73 is a primary priority alluvial site. This site is needed to define a suspected bedrock paleochannel and determine the concentration and extent of contaminants in this area of Section 13. The pilot Denver corehole is a primary priority to define the extent and configuration of Denver sands downgradient of the NBCS. There are currently

no Denver borings or wells in this area of Section 13. The Denver wells are lower priority and installation is dependent upon water quality, hydrologic and geologic data obtained at sites E-63, E-33, and E-34.

Site E-74

Proposed well site E-74 is a primary priority alluvial site. This site is needed to define a suspected bedrock paleochannel and determine the concentration and extent of contaminants in this area of Section 13. The pilot Denver corehole is a primary priority to define the extent and configuration of Denver sands downgradient of the NBCS. There are currently no Denver borings or wells in this area of Section 13. The Denver wells are lower priority and installation is dependent upon water quality, hydrologic and geologic data obtained at sites E-63, E-33, and E-34.

Site E-75

Proposed well site E-75 is for the installation of one primary priority alluvial well. This site is a primary priority. This site will be used to assess the water quality and alluvial hydrogeology upgradient of the Boller well and site E-58.

Site E-76

Proposed well site E-76 is for the installation of one primary priority alluvial well. This site is a primary priority. This site will be used to assess the water quality and alluvial hydrogeology upgradient of the Boller well and site E-58.

APPENDIX C---STATUS

Status

CWP STATUS
07/15/88

P/A = PLUGGED AND ABANDONED TBD = TO BE DETERMINED
DRY = UNSATURATED ALLUVIUM

STATION	SITE	TASK	TARGET	PRIORITY	REMARKS
---------	------	------	--------	----------	---------

CWP STATUS
07/15/88

P/A = PLUGGED AND ABANDONED TBD = TO BE DETERMINED
DRY = UNSATURATED ALLUVIUM

STATION	SITE	TASK	TARGET	PRIORITY	REMARKS
---------	------	------	--------	----------	---------

23218 23219	E-32	36	COREHOLE	PRIMARY	COMPLETED P/A
			1ST SAND	PRIMARY	COMPLETED
			2ND SAND	PRIMARY	COMPLETED

24191	E-33	36	COREHOLE	PRIMARY	COMPLETED P/A
			1ST SAND	PRIMARY	COMPLETED
			2ND SAND	TERTIARY	

37376	E-34	36	COREHOLE	PRIMARY	COMPLETED P/A
			1ST SAND	PRIMARY	COMPLETED
			2ND SAND	TERTIARY	

E-35	36	ELIMINATED; EXISTING COVERAGE SUFFICIENT			
------	----	--	--	--	--

E-36	39	ALLUVIAL	TERTIARY	
		COREHOLE	TERTIARY	
		1ST SAND	TERTIARY	
		2ND SAND	TERTIARY	

E-37	36	ELIMINATED; E-38,EP-71,EP-72 INSTALLED IN LIEU OF SITE			
------	----	--	--	--	--

37374 37379 37380	E-38	39	ALLUVIAL	PRIMARY	COMPLETED
			COREHOLE	PRIMARY	COMPLETED P/A
			1ST SAND	PRIMARY	COMPLETED
			2ND SAND	PRIMARY	COMPLETED

37387 37388	E-39	36	ALLUVIAL	PRIMARY	DRY P/A
			COREHOLE	PRIMARY	COMPLETED P/A
			1ST SAND	PRIMARY	COMPLETED
			2ND SAND	PRIMARY	COMPLETED

37370 37371 37372	E-40	36	ALLUVIAL	PRIMARY	COMPLETED
			COREHOLE	PRIMARY	COMPLETED P/A
			1ST SAND	PRIMARY	COMPLETED
			2ND SAND	PRIMARY	COMPLETED

CWP STATUS
07/15/88

P/A = PLUGGED AND ABANDONED TBD = TO BE DETERMINED
DRY = UNSATURATED ALLUVIUM

STATION	SITE	TASK	TARGET	PRIORITY	REMARKS
	E-41	36	ALLUVIAL COREHOLE 1ST SAND 2ND SAND	SECONDARY TERTIARY TERTIARY TERTIARY	
37369	E-42	36	ALLUVIAL COREHOLE 1ST SAND 2ND SAND	PRIMARY TERTIARY TERTIARY TERTIARY	COMPLETED
	E-43	39	ALLUVIAL COREHOLE 1ST SAND	SECONDARY TERTIARY TERTIARY	
37373 37398 37399	E-44	39	ALLUVIAL COREHOLE 1ST SAND 2ND SAND	PRIMARY PRIMARY PRIMARY TERTIARY TERTIARY TERTIARY	COMPLETED; AQUIFER TEST COMPLETED; OBSERVATION WELL COMPLETED; OBSERVATION WELL
	E-45	39	ALLUVIAL COREHOLE 1ST SAND 2ND SAND	TERTIARY TERTIARY TERTIARY TERTIARY	
37377	E-46	39	ALLUVIAL COREHOLE 1ST SAND 2ND SAND	PRIMARY PRIMARY TERTIARY TERTIARY	COMPLETED COMPLETED P/A
37378	E-47	39	ALLUVIAL COREHOLE 1ST SAND 2ND SAND	PRIMARY PRIMARY TERTIARY TERTIARY	COMPLETED
	E-48	39	ALLUVIAL	SECONDARY	
	E-49	39	COREHOLE 1ST SAND 2ND SAND	TERTIARY TERTIARY TERTIARY	

CWP STATUS
07/15/88

P/A = PLUGGED AND ABANDONED TBD = TO BE DETERMINED
DRY = UNSATURATED ALLUVIUM

STATION	SITE	TASK	TARGET	PRIORITY	REMARKS
37396	E-50	39	ALLUVIAL COREHOLE 1ST SAND	PRIMARY TERTIARY TERTIARY	COMPLETED
	E-51	39	COREHOLE 1ST SAND 2ND SAND	TERTIARY TERTIARY TERTIARY	
37397	E-52	39	ALLUVIAL	PRIMARY	COMPLETED
37367	E-53	39	ALLUVIAL	PRIMARY	COMPLETED; AQUIFER TEST
37400				PRIMARY	COMPLETED; OBSERVATION WELL
37401			COREHOLE 1ST SAND 2ND SAND	PRIMARY TERTIARY TERTIARY TERTIARY	COMPLETED; OBSERVATION WELL
	E-54	39	ALLUVIAL COREHOLE 1ST SAND 2ND SAND	TERTIARY TERTIARY TERTIARY TERTIARY	
37382	E-55	25	ALLUVIAL	PRIMARY	COMPLETED
	E-56	39			ELIMINATED; E-38, EP-71, EP-72 INSTALLED IN LIEU OF SITE
	E-57	39	ALLUVIAL	TERTIARY	
37368	E-58	39	ALLUVIAL	PRIMARY	COMPLETED
37395	E-59	39	ALLUVIAL	PRIMARY	COMPLETED
	E-60	39	ALLUVIAL	TERTIARY	
	E-61	39	ALLUVIAL	TERTIARY	

CWP STATUS
07/15/88

P/A = PLUGGED AND ABANDONED TBD = TO BE DETERMINED
DRY = UNSATURATED ALLUVIUM

STATION	SITE	TASK	TARGET	PRIORITY	REMARKS
	E-62	39	ALLUVIAL	SECONDARY	
37389	E-63	36	ALLUVIAL	PRIMARY	COMPLETED
			COREHOLE	PRIMARY	COMPLETED P/A
37390			1ST SAND	PRIMARY	COMPLETED
			2ND SAND	PRIMARY	
	E-64	39	ALLUVIAL	PRIMARY	DRY P/A
			COREHOLE	TERTIARY	
			1ST SAND	TERTIARY	
			2ND SAND	TERTIARY	
37381	E-65	39	ALLUVIAL	PRIMARY	COMPLETED
			COREHOLE	SECONDARY	
			1ST SAND	SECONDARY	
			2ND SAND	TERTIARY	
37386	E-66	25	ALLUVIAL	PRIMARY	COMPLETED
37385	E-67	25	ALLUVIAL	PRIMARY	COMPLETED
	E-68	25	ALLUVIAL	SECONDARY	
	E-69	36	COREHOLE	PRIMARY	COMPLETED P/A
	E-70	39	ALLUVIAL	SECONDARY	
	E-71	39	ALLUVIAL	SECONDARY	
	E-72	39	ALLUVIAL	SECONDARY	
37391	E-73	39	ALLUVIAL	PRIMARY	COMPLETED
			COREHOLE	PRIMARY	COMPLETED P/A
			1ST SAND	SECONDARY	
			2ND SAND	TERTIARY	
37392	E-74	39	ALLUVIAL	PRIMARY	COMPLETED
			COREHOLE	PRIMARY	COMPLETED P/A
			1ST SAND	SECONDARY	
			2ND SAND	TERTIARY	

CWP STATUS
07/15/88

PVA = PLUGGED AND ABANDONED TBD = TO BE DETERMINED
DRY = UNSATURATED ALLUVIUM

STATION	SITE	TASK	TARGET	PRIORITY	REMARKS
	E-75	39	ALLUVIAL	PRIMARY	DRY PVA
37383	E-76	39	ALLUVIAL	PRIMARY	COMPLETED
	EP-01	25	ALLUVIAL	SECONDARY	
	EP-01A	25	ALLUVIAL	SECONDARY	
27085	EP-02	25	ALLUVIAL	PRIMARY	COMPLETED
27086	EP-03	25	ALLUVIAL	PRIMARY	COMPLETED
23231	EP-04	25	ALLUVIAL	PRIMARY	COMPLETED
	EP-05	25	ALLUVIAL	SECONDARY	
	EP-06	25	ALLUVIAL	SECONDARY	
	EP-07	25	ALLUVIAL	TERTIARY	
	EP-08	25	ALLUVIAL	SECONDARY	
	EP-09	25	ALLUVIAL	TERTIARY	
	EP-10	25	ALLUVIAL	TERTIARY	
24199	EP-11	25	ALLUVIAL	PRIMARY	COMPLETED
	EP-12	25	ALLUVIAL	TERTIARY	
24200	EP-13	25	ALLUVIAL	PRIMARY	COMPLETED
24201	EP-14	25	ALLUVIAL	PRIMARY	COMPLETED
	EP-15	25			ELIMINATED; COMBINED WITH EP-74 CLUSTER
	EP-16	25	ALLUVIAL	SECONDARY	
	EP-17	25	ALLUVIAL	SECONDARY	
	EP-18	25	ALLUVIAL	TERTIARY	

CWP STATUS
07/15/88

P/A = PLUGGED AND ABANDONED TBD = TO BE DETERMINED
DRY = UNSATURATED ALLUVIUM

STATION	SITE	TASK	TARGET	PRIORITY	REMARKS
	EP-19	36	ALLUVIAL COREHOLE 1ST SAND 2ND SAND	SECONDARY PRIMARY SECONDARY SECONDARY	COMPLETED P/A
23226 23236	EP-20	36	ALLUVIAL COREHOLE 1ST SAND 2ND SAND	TERTIARY PRIMARY PRIMARY PRIMARY	COMPLETED P/A COMPLETED COMPLETED
23235	EP-21	36	ALLUVIAL COREHOLE 1ST SAND 2ND SAND	TERTIARY PRIMARY PRIMARY SECONDARY	COMPLETED P/A COMPLETED
	EP-22	36	ALLUVIAL COREHOLE 1ST SAND 2ND SAND	SECONDARY SECONDARY SECONDARY TERTIARY	
23232	EP-23	25	ALLUVIAL	PRIMARY	COMPLETED
	EP-24	25	ALLUVIAL		ELIMINATED; EP-04 INSTALLED IN LIEU OF SITE
	EP-25	36	COREHOLE 1ST SAND	PRIMARY SECONDARY	
23233 23234	EP-26	36	COREHOLE 1ST SAND 2ND SAND	PRIMARY PRIMARY PRIMARY	COMPLETED P/A COMPLETED COMPLETED
23227 23228	EP-27	36	COREHOLE 1ST SAND 2ND SAND	PRIMARY PRIMARY PRIMARY	COMPLETED P/A COMPLETED COMPLETED
	EP-28	36	ALLUVIAL COREHOLE 1ST SAND	SECONDARY PRIMARY PRIMARY	COMPLETED P/A
25048	EP-29	21	ALLUVIAL	PRIMARY	COMPLETED
	EP-30	21	ALLUVIAL	SECONDARY	
	EP-31	21	ALLUVIAL	TERTIARY	

CWP STATUS
07/15/88

P/A = PLUGGED AND ABANDONED TBD = TO BE DETERMINED
DRY = UNSATURATED ALLUVIUM

STATION	SITE	TASK	TARGET	PRIORITY	REMARKS
	EP-33	21	ALLUVIAL	SECONDARY	
			ALLUVIAL	SECONDARY	
			COREHOLE	SECONDARY	
			1ST SAND	SECONDARY	
	EP-32	21	ALLUVIAL	SECONDARY	
	EP-34	21	ALLUVIAL	SECONDARY	
36181	EP-35	1	ALLUVIAL	PRIMARY	COMPLETED
			COREHOLE	PRIMARY	COMPLETED P/A
36182			1ST SAND	PRIMARY	COMPLETED
36183			2ND SAND	PRIMARY	COMPLETED
	EP-36	1	ALLUVIAL	SECONDARY	
	EP-37	1	ALLUVIAL	SECONDARY	
36180	EP-38	1	ALLUVIAL	PRIMARY	COMPLETED
	EP-39	1	ALLUVIAL	SECONDARY	
	EP-40	1			ELIMINATED; EXISTING COVERAGE SUFFICIENT
36177	EP-41	1	ALLUVIAL	PRIMARY	COMPLETED
			COREHOLE	PRIMARY	COMPLETED P/A
36178			1ST SAND	PRIMARY	COMPLETED
36179			2ND SAND	PRIMARY	COMPLETED
	EP-42	19	ALLUVIAL	TERTIARY	
	EP-43	19	COREHOLE	PRIMARY	COMPLETED P/A
26150			1ST SAND	PRIMARY	COMPLETED
	EP-44	19	COREHOLE	PRIMARY	COMPLETED P/A
26154			ALLUVIAL	PRIMARY	COMPLETED
26151			1ST SAND	PRIMARY	COMPLETED
26152			2ND SAND	PRIMARY	COMPLETED
	EP-45	19	1ST H2O	SECONDARY	
	EP-46	19	1ST H2O	SECONDARY	
27084	EP-47	19	1ST H2O	PRIMARY	COMPLETED

CWP STATUS
07/15/88

P/A = PLUGGED AND ABANDONED TBD = TO BE DETERMINED
DRY = UNSATURATED ALLUVIUM

STATION	SITE	TASK	TARGET	PRIORITY	REMARKS
	EP-48	19	1ST H2O	SECONDARY	
	EP-49	19	COREHOLE	PRIMARY	COMPLETED P/A B1; INSTLLN @ B2
26155			1ST SAND	PRIMARY	COMPLETED
26156			2ND SAND	PRIMARY	COMPLETED
	EP-50	19	COREHOLE	SECONDARY	
			1ST H2O	SECONDARY	
			1ST SAND	SECONDARY	
			2ND SAND	SECONDARY	
	EP-51	19	ELIMINATED; EP-52 INSTALLED IN LIEU OF SITE		
	EP-52	19	COREHOLE	PRIMARY	COMPLETED P/A
26149			1ST SAND	PRIMARY	COMPLETED
			2ND SAND	SECONDARY	
23220	EP-53	44	ALLUVIAL	PRIMARY	COMPLETED
			COREHOLE	PRIMARY	COMPLETED P/A
23221			1ST SAND	PRIMARY	COMPLETED
23222			2ND SAND	PRIMARY	COMPLETED
26148	EP-54	44	ALLUVIAL	PRIMARY	COMPLETED
	EP-55	44	ALLUVIAL	PRIMARY	DRY P/A
	EP-56	44	ALLUVIAL	PRIMARY	DRY P/A
			COREHOLE	PRIMARY	COMPLETED P/A
26153			1ST SAND	SECONDARY	
			2ND SAND	PRIMARY	COMPLETED
	EP-57	44	ELIMINATED; EP-56 INSTALLED IN LIEU OF SITE		
	EP-58	44	ELIMINATED; EXISTING COVERAGE SUFFICIENT		
	EP-59	19	1ST H2O	SECONDARY	
	EP-60	44	ELIMINATED; COMBINED WITH EP-49		
	EP-61	44	ELIMINATED; EXISTING CLUSTER ADEQUATE FOLLOWING REVIEW		
	EP-62	44	ALLUVIAL	PRIMARY	DRY P/A
			COREHOLE	PRIMARY	COMPLETED P/A
34011			1ST SAND	PRIMARY	COMPLETED
			2ND SAND	TBD	

CWP STATUS
07/15/88

P/A = PLUGGED AND ABANDONED TBD = TO BE DETERMINED
DRY = UNSATURATED ALLUVIUM

STATION	SITE	TASK	TARGET	PRIORITY	REMARKS
=====					
	EP-63	44			ELIMINATED; EXISTING CLUSTER ADEQUATE FOLLOWING REVIEW
=====					
	EP-64	44	ALLUVIAL	SECONDARY	
=====					
	EP-65	44	ALLUVIAL	PRIMARY	DRY P/A
			COREHOLE	PRIMARY	COMPLETED P/A
34012			1ST SAND	PRIMARY	COMPLETED
34013			2ND SAND	PRIMARY	COMPLETED
=====					
	EP-66	44	ALLUVIAL	PRIMARY	DRY P/A
			COREHOLE	PRIMARY	COMPLETED P/A
03012			1ST SAND	PRIMARY	COMPLETED
			2ND SAND	SECONDARY	
=====					
35087	EP-67	44	ALLUVIAL	PRIMARY	COMPLETED
			COREHOLE	PRIMARY	COMPLETED P/A
35088			1ST SAND	PRIMARY	COMPLETED
35089			2ND SAND	PRIMARY	COMPLETED
=====					
	EP-68	44			ELIMINATED; NOT REQUIRED FOR CURRENT STUDY
=====					
	EP-69	44			ELIMINATED; NOT REQUIRED FOR CURRENT STUDY
=====					
	EP-70	44			ELIMINATED; NOT REQUIRED FOR CURRENT STUDY
=====					
	EP-71	44	ALLUVIAL	PRIMARY	DRY P/A
			COREHOLE	PRIMARY	COMPLETED P/A
22079			1ST SAND	PRIMARY	COMPLETED
22080			2ND SAND	PRIMARY	COMPLETED
=====					
	EP-72	44	ALLUVIAL	PRIMARY	DRY P/A
			COREHOLE	PRIMARY	COMPLETED P/A
23229			1ST SAND	PRIMARY	COMPLETED
23230			2ND SAND	PRIMARY	COMPLETED
=====					
	EP-73	44			ELIMINATED; COMBINED WITH EP-53
=====					
24196	EP-74	44	ALLUVIAL	PRIMARY	COMPLETED
			COREHOLE	PRIMARY	COMPLETED P/A
24197			1ST SAND	PRIMARY	COMPLETED
24198			2ND SAND	PRIMARY	COMPLETED
=====					
23223	EP-75	44	ALLUVIAL	PRIMARY	COMPLETED
			COREHOLE	PRIMARY	COMPLETED P/A
23224			1ST SAND	PRIMARY	COMPLETED
23225			2ND SAND	PRIMARY	COMPLETED
=====					

CWP STATUS
08/25/88

P/A = PLUGGED AND ABANDONED TBD = TO BE DETERMINED
DRY = UNSATURATED ALLUVIUM

STATION	SITE	TASK	TARGET	PRIORITY	REMARKS
=====					
	EP-76	36	COREHOLE	PRIMARY	COMPLETED P/A
			1ST SAND	SECONDARY	
			2ND SAND	SECONDARY	
			3RD SAND	SECONDARY	
=====					
PIEZOMETERS		36	ALLUVIAL	PRIMARY	COMPLETED
23212	P-3				
23213	P-5				
23214	P-7				
23215	P-8				
23216	P-10				
23217	P-12				
24192	P-14				
24193	P-16				
24194	P-17				
24195	P-18				
=====					
01701	HSBF-1	11	ALLUVIAL	PRIMARY	COMPLETED
=====					
01702	HSBF-2	11	ALLUVIAL	PRIMARY	COMPLETED
=====					
05004	S-2	22	ALLUVIAL	PRIMARY	COMPLETED
=====					
	S-1	26	DENVER	PRIMARY	
=====					
35077	S-2	26	DENVER	PRIMARY	COMPLETED
=====					
	S-3	26	DENVER	PRIMARY	
=====					
	S-4	26	DENVER	PRIMARY	
=====					
35079	S-5	26	ALLUVIAL	PRIMARY	COMPLETED
35081	-6		ALLUVIAL	PRIMARY	COMPLETED
35080	-7		DENVER	PRIMARY	COMPLETED
	-8		DENVER	PRIMARY	
=====					
35159	S-9	26	ALLUVIAL	PRIMARY	COMPLETED
	-10		DENVER	PRIMARY	
	-11		DENVER	PRIMARY	
=====					
35158	S-12	26	ALLUVIAL	PRIMARY	COMPLETED
=====					
35083	S-13	26	DENVER	PRIMARY	COMPLETED
35084	-14		DENVER	PRIMARY	COMPLETED
=====					

CWP STATUS
08/25/88

PVA = PLUGGED AND ABANDONED TBD = TO BE DETERMINED
DRY = UNSATURATED ALLUVIUM

STATION	SITE	TASK	TARGET	PRIORITY	REMARKS
02050	S-15	26	ALLUVIAL	PRIMARY	COMPLETED
02052	S-16	26	ALLUVIAL	PRIMARY	COMPLETED
01069	S-17	26	ALLUVIAL	PRIMARY	COMPLETED
01070	S-18	26	ALLUVIAL	PRIMARY	COMPLETED
33076	WT33-1	38	ALLUVIAL	PRIMARY	COMPLETED
33077	WT33-2	38	ALLUVIAL	PRIMARY	COMPLETED
33078			ALLUVIAL	PRIMARY	COMPLETED
33079			ALLUVIAL	PRIMARY	COMPLETED
33074	WT33-3	38	ALLUVIAL	PRIMARY	COMPLETED
33075			ALLUVIAL	PRIMARY	COMPLETED
04038	WT4-1	38	ALLUVIAL	PRIMARY	COMPLETED
04039			ALLUVIAL	PRIMARY	COMPLETED
04037	WT4-2	38	ALLUVIAL	PRIMARY	COMPLETED
04045	WT4-3	38	ALLUVIAL	PRIMARY	COMPLETED
04046			ALLUVIAL	PRIMARY	COMPLETED
04047			ALLUVIAL	PRIMARY	COMPLETED
04040	WT4-4	38	ALLUVIAL	PRIMARY	COMPLETED
04044	WT4-5	38	ALLUVIAL	PRIMARY	COMPLETED
04036	WT4-6	38	ALLUVIAL	PRIMARY	COMPLETED
04030	WT4-7	38	ALLUVIAL	PRIMARY	COMPLETED
04031	WT4-8	38	ALLUVIAL	PRIMARY	COMPLETED
04032	WT4-9	38	ALLUVIAL	PRIMARY	COMPLETED
04033	WT4-10	38	ALLUVIAL	PRIMARY	COMPLETED
04035	WT4-11	38	ALLUVIAL	PRIMARY	COMPLETED
04041	WT4-12	38	ALLUVIAL	PRIMARY	COMPLETED

CWP STATUS
08/25/88

P/A = PLUGGED AND ABANDONED TBD = TO BE DETERMINED
DRY = UNSATURATED ALLUVIUM

STATION	SITE	TASK	TARGET	PRIORITY	REMARKS
=====					
04042	WT4-13	38	ALLUVIAL	PRIMARY	COMPLETED
04043			ALLUVIAL	PRIMARY	COMPLETED
=====					
03011	WT3-1	38	ALLUVIAL	PRIMARY	COMPLETED
=====					
09010	WT9-1	38	ALLUVIAL	PRIMARY	COMPLETED
=====					
09011	WT9-2	38	ALLUVIAL	PRIMARY	COMPLETED
09012			ALLUVIAL	PRIMARY	COMPLETED
=====					
	WT9-3	38	ALLUVIAL	PRIMARY	
=====					
09008	WT9-4	38	ALLUVIAL	PRIMARY	COMPLETED
09009			ALLUVIAL	PRIMARY	COMPLETED
=====					
09013	WT9-5	38	ALLUVIAL	PRIMARY	COMPLETED
09014			ALLUVIAL	PRIMARY	COMPLETED
=====					
25041	25041	42	ALLUVIAL	PRIMARY	COMPLETED
=====					
25042	25042	42	ALLUVIAL	PRIMARY	COMPLETED
=====					
25043	25043	42	ALLUVIAL	PRIMARY	COMPLETED
=====					
25044	25044	42	ALLUVIAL	PRIMARY	COMPLETED
=====					
25046	25046	42	ALLUVIAL	PRIMARY	COMPLETED
=====					
25047	25047	42	ALLUVIAL	PRIMARY	COMPLETED
=====					

APPENDIX D--DEEP WELL METHODOLOGY

07/19/88

DEEP WELL METHODOLOGY

One of the objectives of the RMA Remedial Investigation was to define the maximum vertical extent of ground-water contamination. This was accomplished to a limited degree by interpretation of existing ground-water monitoring wells. In many areas of RMA the sampling of the deepest existing monitoring wells resulted in the detection of inorganic and/or organic constituents.

The Composite Well Program was devised to provide a mechanism to select, prioritize, and install additional ground-water monitoring wells that would delineate the areal and vertical extent of contamination. With respect to definition of the vertical extent of contamination, the Composite Well Program identified locations where RMA contaminants were detected in the lowest available Denver Fm wells in source and plume areas. Based on this information a priority for the installation of deeper wells was established.

During the process by which locations and depths for additional monitoring wells were selected, the contractor teams developed a formalized approach to the delineation of the vertical extent of ground-water contamination. The strategy developed during the design and implementation of the Composite Well Program is shown in the flowchart presented as Figure D-1. Although this procedure could not be strictly followed during the execution of the Composite Well Program, the concept of defining the vertical extent of contamination with the use of additional monitoring wells was established.

Ground-water monitoring wells installed in cluster configurations were constructed in most of the major source and plume areas. Specifically deep monitoring wells were installed in the vicinity of the NBCS (Sections 23 and 24), the NWBCS (Section 22), Basin A (Section 36), Basins B through F (Sections 35 and 26), and the offpost area. After water quality data resulting from the sampling of these wells is available, the need for the installation of deeper wells at these locations will be assessed.

The purpose of efforts directed towards installation of deeper wells during the Composite Well Program was to provide information to fill significant

07/19/88

data deficiencies perceived to be required to complete the Remedial Investigation. Additional refinement of the vertical distribution of RMA contaminants in the Denver Fm is not perceived to be data necessary to complete the Remedial Investigation, but may be data required for the completion of the Feasibility Study. During these efforts the process shown in the flow chart (Figure D-1) will be used to identify locations for deeper wells.




Figure D-1
EVALUATION OF WELL NETWORK TO
IDENTIFY THE NEED FOR DEEP WELLS

SOURCE: ESE, 1987

Prepared for:
U.S. Army Program Manager's Office
For Rocky Mountain Arsenal

Aberdeen Proving Ground, Maryland

32

33

5

4


33

34

4

3

37356
△



34

35

37364

△

37357


△

2

3

37356
△

37354
△




35

36

2

1




36

31

1

6




31

32

6

5

Ø BRIAN CAN



32

33

Ø BRIAN CANAL

5

4

33

34

4

3


8


9

17


16

E RIVER





11



12

7

E-59

37395

37344

△

△ 37340

E-75

37320

E-54

E-53

37367

37400

37401

E-76

37383

37322

△ 37321

13

18

E-73

37391

E-46

37377

E-74

37392

E-47

37378

E-48

37327


E-49

E-43

37310

37323

37309



7

8

SECOND CREEK

18

17


8

9

SECOND CREEK

17

16



9

10

16

15

SOUTH PLATE RIVER

37361 Δ

20

21


HWY 85


37360
Δ


29

BURLINGTON DITCH

28







E-46 7377
E-74 37392
E-47 37378
E-48
37327 E-49


E-43

DARY CONTAINMENT SYSTEM

E-34

37376

E-36



P-13
24200

053
054
055
056
057
058
059
060
061
062
063
064
065
066
067
068
069
070
071
072
073
074
075
076
077
078
079
080
081
082
083
084
085
086
087
088
089
090
091
092
093
094
095
096
097
098
099
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
841
842
843
844
845
846
847
848
849
850
851
852
853
854
855
856
857
858
859
860
861
862
863
864
865
866
867
868
869
870
871
872
873
874
875
876
877
878
879
880
881
882
883
884
885
886
887
888
889
890
891
892
893
894
895
896
897
898
899
900
901
902
903
904
905
906
907
908
909
910
911
912
913
914
915
916
917
918
919
920
921
922
923
924
925
926
927
928
929
930
931
932
933
934
935
936
937
938
939
940
941
942
943
944
945
946
947
948
949
950
951
952
953
954
955
956
957
958
959
960
961
962
963
964
965
966
967
968
969
970
971
972
973
974
975
976
977
978
979
980
981
982
983
984
985
986
987
988
989
990
991
992
993
994
995
996
997
998
999
1000.

EP-74

EP-18

080 125 081 082 083 084 085 086 087 001 002

018
019
020

002
003

006
007
008

30

030
031

EP-29
25048

EP-31 EP-34

003
004
005

014
Δ015
016

ROCKY MOUNTAIN ARSENAL

20

017
Δ018
019

01
Δ


001
Δ

006
Δ007
008

29

002
Δ003

003
Δ004
005



21

SECOND CREEK

28

27

4413000

4412000

4411000

29

28

BURLINGTON DITCH

O'BRIAN CANAL


37359
△37358
△067
△024
△


32


033
△052
△026
△068
△013
△034
△059
△058
△007
△072
△030
△002
△


WT33-1

015
△016
△011
△012
△013
△014
△015
△016
△017
△018
△019
△020
△021
△022
△023
△024
△025
△026
△027
△028
△029
△030
△031
△032
△033
△034
△035
△036
△037
△038
△039
△040
△041
△042
△043
△044
△045
△046
△047
△048
△049
△050
△051
△052
△053
△054
△055
△056
△057
△058
△059
△060
△061
△062
△063
△064
△065
△066
△067
△068
△069
△070
△071
△072
△073
△074
△075
△076
△077
△078
△079
△080
△081
△082
△083
△084
△085
△086
△087
△088
△089
△090
△091
△092
△093
△094
△095
△096
△097
△098
△099
△100
△101
△102
△103
△104
△105
△106
△107
△108
△109
△110
△111
△112
△113
△114
△115
△116
△117
△118
△119
△120
△121
△122
△123
△124
△125
△126
△127
△128
△129
△130
△131
△132
△133
△134
△135
△136
△137
△138
△139
△140
△141
△142
△143
△144
△145
△146
△147
△148
△149
△150
△151
△152
△153
△154
△155
△156
△157
△158
△159
△160
△161
△162
△163
△164
△165
△166
△167
△168
△169
△170
△171
△172
△173
△174
△175
△176
△177
△178
△179
△180
△181
△182
△183
△184
△185
△186
△187
△188
△189
△190
△191
△192
△193
△194
△195
△196
△197
△198
△199
△200
△201
△202
△203
△204
△205
△206
△207
△208
△209
△210
△211
△212
△213
△214
△215
△216
△217
△218
△219
△220
△221
△222
△223
△224
△225
△226
△227
△228
△229
△230
△231
△232
△233
△234
△235
△236
△237
△238
△239
△240
△241
△242
△243
△244
△245
△246
△247
△248
△249
△250
△251
△252
△253
△254
△255
△256
△257
△258
△259
△260
△261
△262
△263
△264
△265
△266
△267
△268
△269
△270
△271
△272
△273
△274
△275
△276
△277
△278
△279
△280
△281
△282
△283
△284
△285
△286
△287
△288
△289
△290
△291
△292
△293
△294
△295
△296
△297
△298
△299
△300
△301
△302
△303
△304
△305
△306
△307
△308
△309
△310
△311
△312
△313
△314
△315
△316
△317
△318
△319
△320
△321
△322
△323
△









002
A

006
A007
008

29

002
A003

003
A004
005

EP-34
EP-33
P-33

009
A010
011

009
A010
011

001
A002
003

32

31

005
A006
007

001
A

003
A004

003 A004
005 A001

29

28

002
A003

001
A002
003

32


33


28


27


33


A large rectangular area, likely a placeholder for a drawing or photograph. It is defined by a vertical line on the left and a vertical line on the right. The number '34' is written in the top right corner. A wavy line runs along the bottom edge of the rectangle.











003 Δ004
005 Δ001

5

001
Δ

002
Δ

5-2
●
00004

002
Δ003

003
Δ004
005

8

003
Δ004
005

001
Δ

4409000

4408000

4407000

4406000

3

4

10

9

37366



006
△

8

073
△

076
△

035
△

017
△

9

001
△

045
△

036
△

066
△

032
△

029
△

006
△

005
△

025
△

037
△

060
△

028
△

007
△

17

063
△

16

507000

508000

042
Δ043
WT4-13

ROCKY MOUNTAIN ARSENAL

WT 3-1

010
Δ
WT9-1

9

002
Δ003
004

011
Δ012
WT9-2

WT9-3

006
Δ

005
Δ

008
Δ009
WT9-4

WT9-5

16

15

WT 3-1

011
Δ012
013

008
Δ

11

007
Δ

002
Δ003
HAVANA ST. INTERCEPTER Δ004

HAVANA POND


HAVANA ST. INTERCEPTER

14

51000

511000

512000



026
Δ 027
028

024
Δ 024
025

051
Δ

021
Δ 022
023

008
Δ

000
Δ

12

009
Δ


007
Δ

009
Δ

006
Δ

005
Δ

07
Δ



HAVANA PONDS

HAVANA ST. INTERCEPTER

001
Δ

002
Δ 003
004

PEOR

001
Δ

13

8

9

003
▲004
005

37366

002
Δ

FIRST CREEK

17

16

Plate 1 COMPOSITE W

DRAWING NO. DRAWING TITLE

1" 1000'

ESE PROJECT NUMBER SCALE

④

③

W.B. Updated

②

J.L. P.G.

Updated 1/13/88

① Revised

3/87

DRAWN/REVISED

BY CHK'D

517000

k 26)

k 38)

4407000

4406000

4405000

9

10

37366

FIRST CREEK

16

15



FILE LOCATION : T4B-4

Plate 1 COMPOSITE WELL PROGRAM PROPOSED LOCATION

DRAWING NO. DRAWING TITLE

ESE PROJECT NUMBER SCALE

1" 1000'

④

③

W.B. Updated 7/88

②

JL. P.G.

Updated 1/13/88

① Revised

3/87 1-87

9-86

DRAWN/REVISED BY CHK'D DATE

Prepared for:
U.S. Army Program Manager's Office
For Rocky Mountain Arsenal
Aberdeen Proving Ground, Maryland

**ESE ENVIRONMENTAL SCIENCE
AND ENGINEERING, INC.**

AN RSC COMPANY

D. Stephens

1-87

APPROVED FOR ISSUE BY


DATE

32

33

5

4



33

34

4

A line drawing of a wavy, irregular shape, possibly a stylized letter 'S' or a path, with a horizontal line passing through it. The shape is composed of two main parts: a lower, more vertical section on the left and a larger, more horizontal section on the right. The lines are slightly jagged, giving it a hand-drawn appearance. A horizontal line crosses the lower part of the shape.

356
△

34

35

37364



37357



3

2

356



37354



35

36

2

1

37357
△


37354
△

36

31

1

6




31


32

Ø BRIAN CANAL

6

5





Ø BRIAN CANAL

5

33

34

4

3

8


9

17

16

37363





37356
△

37354
△

37353
△

37350
△

11

37352
△

37349
△

37341
△

37368 △

37397 △

37348
△


37347
△

14

37342
△

37346
△

37396
△



12

7

37341 Δ

37368 Δ

37397 Δ

37344 Δ

37395 Δ

Δ
37367


Δ
37383

37320
Δ 37322 37321

Δ 37340

13

18



8

SECOND CREEK

17

9

10

16

15

17

16

SOUTH PLATTE RIVER

20

37361 Δ


21

BURLINGTON

HWY 85

37360
Δ

01



15

37336

37345

~~Δ~~ 37082

21

22

BURLINGTON DITCH

O'BRIEN CANAL

37385

37382^Δ

37386

37332

▲

059 ▲ 06

059

01

.....

A016

0704

31

1



00

312

/

1

1

100

053

▲

A 062

A 062
T 80U1

37360
Δ


020,021,022
023,024,025
032,037,038,041

37335 A

37334

011


A 062
NORTHWEST BOUN



37367 37383 37322 37321

14

13




FIRST CREEK

NORTH BOUNDARY CONTAINMENT SYSTEM


23

24



13

18



18

17

27

014
Δ015
016

ROCKY MOUNTAIN ARSENAL

19

20

009
Δ

008
Δ

007
Δ

017
Δ018
019

011
Δ

005
Δ

006
Δ

004
Δ

003
Δ

002
Δ

002
Δ

006
007

17

16

ROCKY MOUNTAIN ARSENAL


20

21

SECOND CREEK

000
4


011
A





16


15











003
△

001
△

002
△

002
△

30

006
△007
008

29

002
△003

003
△004
005

012
△

001
△

009
△010
011

501
△

31

009
△010
011

32

001
△002
003

005
006 △006
007

001
△

29

002
△003

28


32

001
△002
003


33


000007
1


33





IRONDALE CONTAINMENT SYSTEM











5

4

001
Δ

Δ
004

002
Δ003

8

9

4408000

4408000

4407000

3

4



10

9



9

010
△

10

002
△003
004

001
△

011
△012

006
△

005
△

008
△009

007
△

16

15

509000

510000

5

10

11

008
Δ

007
Δ

HAVANA ST. INTERCEPTER Δ

002
Δ 003
004

HAVANA PONDS

HAVANA ST. INTERCEPTER


15


14


510000

511000

512000







104

8

9

003
Δ 004
005

37366

002
Δ

FIRST CREEK

17

16

Plate 2

85930-046

ON AND OFF

DRAWING NO. DRAWING TI

85930 1"

ESE PROJECT NUMBER SC/

④

③


②

① Revised J.L., 1-13-88

DRAWN/REVISED BY CI

1000

517000



FILE LOCATION :

Plate 2

85930-046 ON AND OFFPOST GROUND WATER MONITORING WELL LOCATION MAP, FEB. 1987
DRAWING NO. DRAWING TITLE

85930	1" 1000'
ESE PROJECT NUMBER	SCALE
④	
③	
②	W B Updated 7/88
① Revised J.L., P.C.	3/87 1-87
	9-86
DRAWN/REVISED	BY CHK'D DATE

ESE ENVIRONMENTAL SCIENCE AND ENGINEERING, INC.
AN **RSC** COMPANY

D. Stephens	1-87
APPROVED FOR ISSUE BY	DATE

R68W R67W

13

24

R67W

18

17

19

20

17

20

16

15

21

22

15

14

22

23

South Platte River


4900

4910

4920

4930

4940



R67W | R66W

13

river

24

4940

4950

R67W | R66W

18

19

17

20

24

25

19

20

30

29

20

21

29

28

21

22

28


27

4930

494

4950

4960



South Platte

23

4900

4910

4920

4930

4940

4950

4960

26

4970

4980

4940

4940

4950


4930

4940

4950

4960

4990



19

2

30

2

5000
5010
5030

20

29

25

36

30

29

31

32

29


32


28

27

33

34






27


26

35

34



30




Creek

31

29

32



T1S

T1S
T2S

1

12

6


5


7


8


5


8












T1S
T2S



13


24


18


19


17


20

















5130

17

5150

5160

5170


5180

5190


20


5200


25





36












RMA BOUND



T2S
T3S

36

5070

5080

5070

1

5090

5100

5090

5100

5090
5080

5080


5090


5100


5110


5120


12

















31

5210

5220

5230

5240

5250

32

6

5220

5230

5240

5260

5250

5270

5280

5290

5300

5310

5

5290

5270

5280

5250

8

BOUNDARY

T2S

T3S

32

5220

5230

5240

5250

5

5290

5260

5270

5280

5250

5250

5260

5280

5290

5300

5310

8

12


5110




5120

5130


5110

T68W R67W





Scale In Feet




EXPLANATION

Contour Interval 10

Elevations In Feet

4000





PLANATION

Contour Interval Equals Ten Feet
Elevations In Feet Above Mean Sea Level

12

5240

5300

5310

7


R67W | R66W

PI

DRAWING

ESE PRO

DRAWN



RMA BEDROCK ELEVATION CONTOUR MAP

Plate 3

DRAWING NO. DRAWING TITLE

1" = 1000'

ESE PROJECT NUMBER SCALE

ESE ENVIRONMENTAL SCIENCE
AND ENGINEERING, INC.
AN RMI COMPANY

AT, Jr., MJR

DRAWN REVISED BY CHK'D DATE

APPROVED FOR ISSUE BY

4/88
DATE

9

10

37355 X

37363 X

37351 X

16

15

37354 X

37353 X

37350 X

10

11

37352 X

37349 X

37351 X

37348 X

37347 X


15


14

37346 X

37343, 365 X

37313 X





7

37340


37320 37321.122

18

37392

37378

37327



37363 X

37351 X

16

15

37361 X

37336

37341

21

22

37382

3

37333

22005

37331

2


37335 X


37360 X


37330

22019

2








37320 X
37321.122

18

37392 37378

37327





17

19015 X

20

19017 X





37336
22059 X

37333 X

22005

37331

37330

22021, 23, 24 X
22023

22043

22008
27062 X

27063

27064

27068

27071
27002

27072

27069 X

27077

27076

27075

27074 X
27074

27003 X
27003

27053, 54, 55 X

27073

27030
27031

27051 X

27049 X

27040 X

27024

27026

27028

23185-187 X

23108 X
23108

26117 X

27016 X
27016

26083, 84 X

26076 X

26008 X

26061 X

26006 X

26071, 72 X

26066, 67 X

23142 X
23142

23191-193 X

23054 X

23049 X
23049

23188-190 X
23189

230

23179-181
231

26

26

34

34008, 9 X

34508 X

34005, 6 X

34507 X


35037, 38, 39 X

35

35034, 36 X

35016, 1

35056 X



24063

24094

24089 X

24112 X

19003 X

24081

24086

19001 X

25018 X

30

25011.13.14 X

30009.11 X

25038.39 X

31

36121.122 X

31005 X

36090 X

36154 X

36084 X

36069 X

29

32002 X

32

33016 X

33030.32 X

34515 X

34002.3 X

33075 X

33002 X

04038 X

04024 X 04021 X 04014 X

03518 X

04007.3.9 X 4

3

04027 X

03002.3.4 X

04010.11 X

04045 X

04030 X

04044 X

03523 X

04041 X

03008 X

04042 X

09010 X

9

10

09002.3 X

09011 X

09006 X

35056 X

35058 X

34504 X

34515 X

34002.3 X

35052.1

03518 X

3

02045 X

02018.19 X

02014 X

002.3.4 X

03005.6 X

02037.38.39 X

02025 X

02008.9.0 X

02034.35.36

03523 X


03008 X

02020.21 X

02011.12 X

10

11



35058 X

35029 X

35058 X

36056 X

36065.66 X

36076 X

35052.54 X

36110 X

35013 X

36001 X

01020 X

02046 X

2

02018.19 X

02030.31 X

02014 X

02037.38.39 X

0102 X

01017 X

02025 X

01017 X

01048 X

02034.35.36 X

01015 X

01027 X

01050 X

02020.21 X

01024.25 X


02011.12 X

11

12

12002.3.4 X

11002.4 X



75 X

36119 X

01006 X

06003.4.5 X

6

5

01036.37 X

01041.43 X


06002 X

21.22 X

7

07004 X

8



5

05001 X

07004 X

8

08003.5 X

37366 X

09010 X

9

10

09002.3 X

09011 X

09006 X 09005 X

09008 X

09013 X

16

15

TASKS 36, 39, 25, AND 44 ALL WELLS

- △ TASK 36 WELLS (⊕ NOT YET SURVEYED)
- ▢ TASK 39 WELLS (⊕ NOT YET SURVEYED)
- TASK 25 WELLS
- ⊗ TASK 44 WELLS

Plate 4
GROUND-WATER MONITORING NETWORK, SPRING 1987

10

11

11002.4 8

15

14

01024.25 X

12

12002.3.4 X

11002.4 X

13

07004 X

7

09001 X

18

07004 X

8

08003.5 X

37366 X

17

TASK 36, 39, 25, AND 44 WELLS

3.00B+0